


# TOWN OF CLINTON, MASSACHUSETTS

## STREETSCAPE IMPROVEMENTS


### HIGH STREET & CHURCH STREET

JULY 2020




BOARD OF SELECTMEN  
WILLIAM F. CONNOLLY, JR.  
SEAN J. KERRIGAN  
EDWARD J. DEVAULT  
MICHAEL J. DZIOKONSKI  
JOHN J. BOISONEAU

DEPARTMENT OF PUBLIC WORKS  
CHRISTOPHER MCGOWN, SUPERINTENDENT



PROJECT LOCATION

#### LOCATION MAP



LENGTH OF PROJECT = 1821± FEET HIGH ST  
816± FEET CHURCH ST

#### INDEX

SHEET NO.	DESCRIPTION
1	TITLE SHEET & INDEX
2	LEGEND & ABBREVIATIONS
3	KEY PLAN
4-9	CONSTRUCTION DETAILS
10-11	TYPICAL SECTIONS
12-17	CONSTRUCTION PLANS
18-23	CURB TIE AND BASELINE PLANS
24-26	PROFILE - HIGH STREET
27	PROFILE - CHURCH STREET WEST
28	PROFILE - CHURCH STREET EAST
29-34	GRADING PLANS
35-40	SIGN & PAVEMENT MARKING PLANS
41	TRAFFIC SIGN SUMMARY
42-44	TEMPORARY TRAFFIC CONTROL PLANS
45-49	LANDSCAPE PLANS
50-51	LANDSCAPE DETAIL AREAS
52-54	LANDSCAPE DETAILS
55-60	UTILITIES PLANS
L1-L7	LIGHTING PLANS
IR-1.0 - IR-2.1	IRRIGATION PLANS

THE MASSACHUSETTS DEPARTMENT OF TRANSPORTATION 2020 STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES, THE OCTOBER 2017 CONSTRUCTION STANDARD DETAILS, THE 2015 OVERHEAD SIGNAL STRUCTURE AND FOUNDATION STANDARD DRAWINGS, MASSDOT TRAFFIC MANAGEMENT PLANS AND DETAIL DRAWINGS, THE LATEST MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS WITH MASSACHUSETTS AMENDMENTS, THE 1990 STANDARD DRAWINGS FOR SIGNS AND SUPPORTS, THE 1968 STANDARD DRAWINGS FOR TRAFFIC SIGNALS AND HIGHWAY LIGHTING, AND THE LATEST EDITION OF THE AMERICAN STANDARD FOR NURSERY STOCK, WILL GOVERN.

PREPARED BY:  
**BETA**  
www.BETA-Inc.com

ISSUE DATE: JULY, 2020



THOMAS J. LOUGHLIN  
CIVIL  
No. 46491  
REGISTERED PROFESSIONAL ENGINEER













































































































REGISTERED PROFESSIONAL





















DATE

































PAVEMENT MARKINGS AND  
SIGNING SYMBOLS

GENERAL SYMBOLS

EXISTING	PROPOSED	DESCRIPTION
 JB	 JB	JERSEY BARRIER
 CB	 CB	CATCH BASIN
 CB	 CB	CATCH BASIN CURB INLET
 FP	 FP	FLAG POLE
 GP	 GP	GAS PUMP
 MB	 MB	MAIL BOX
		POST SQUARE
		POST CIRCULAR
 WELL	 WELL	WELL
 EHH	 EHH	ELECTRIC HANDHOLE
		FENCE GATE POST
 GG	 GG	GAS GATE
 BHL #	 BHL #	BORING HOLE
 MW #	 MW #	MONITORING WELL
 TP #	 TP #	TEST PIT
		HYDRANT
		LIGHT POLE
 CO.BD.		COUNTY BOUND
		GPS POINT
		CABLE MANHOLE
		DRAINAGE MANHOLE
		ELECTRIC MANHOLE
		GAS MANHOLE
		MISC MANHOLE
		SEWER MANHOLE
		TELEPHONE MANHOLE
		WATER MANHOLE
 MHB	 MHB	MASSACHUSETTS HIGHWAY BOUND
 MON		MONUMENT
 SB		STONE BOUND
 TB		TOWN OR CITY BOUND
 Δ		TRAVERSE OR TRIANGULATION STATION
 TPL or GUY	 TPL or GUY	TROLLEY POLE OR GUY POLE
 HTP		TRANSMISSION POLE
 UFB	 UFB	UTILITY POLE W/ FIREBOX
 UPDL	 UPDL	UTILITY POLE WITH DOUBLE LIGHT
 ULT	 ULT	UTILITY POLE W / 1 LIGHT
 UPL	 UPL	UTILITY POLE
		BUSH
		TREE
		STUMP
		SWAMP / MARSH
 WG	 WG	WATER GATE
 PM	 PM	PARKING METER
		OVERHEAD CABLE/WIRE
		CURBING
 100 99		CONTOURS (ON-THE-GROUND SURVEY DATA)
 100 99		CONTOURS (PHOTOGRAMMETRIC DATA)
		UNDERGROUND DRAIN PIPE (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND ELECTRIC DUCT (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND GAS MAIN (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND SEWER MAIN (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND TELEPHONE DUCT (DOUBLE LINE 24 INCH AND OVER)
		UNDERGROUND WATER MAIN (DOUBLE LINE 24 INCH AND OVER)
		BALANCED STONE WALL
		GUARD RAIL - STEEL POSTS
		GUARD RAIL - WOOD POSTS
 x		CHAIN LINK OR METAL FENCE
 o		WOOD FENCE
		HAY BALES/SILT FENCE
		TREE LINE
 - - - -		SAWCUT LINE
 - - - -		TOP OR BOTTOM OF SLOPE
 - - - -		LIMIT OF EDGE OF PAVEMENT OR COLD PLANE AND OVERLAY
 - - - -		BANK OF RIVER OR STREAM
 - - - -		BORDER OF WETLAND
 - - - -		100 FT WETLAND BUFFER
 - - - -		200 FT RIVERFRONT BUFFER
 - - - -		STATE HIGHWAY LAYOUT
 - - - -		TOWN OR CITY LAYOUT
 - - - -		COUNTY LAYOUT
 - - - -		RAILROAD SIDELINE
 - - - -		TOWN OR CITY BOUNDARY LINE
 e		PROPERTY LINE OR APPROXIMATE PROPERTY LINE
 - - - -		EASEMENT

EXISTING	PROPOSED	DESCRIPTION
CW		CROSSWALK, 2 - 12" WHITE LINES (8' WIDTH)
SL		STOP LINE - 12" WHITE LINE 4' BEHIND CW (TYP.)
SWL		SOLID WHITE LINE - 6"
SWCHL		SOLID WHITE CHANNELIZING LINES - 12" (SPACING NOTED)
SWGL		SOLID WHITE GORE LINE 6" @ 45°, (SPACING NOTED)
SWPL		SOLID WHITE PARKING LINE - 6"
BWL		BROKEN WHITE LINE - 6"
DWLex		DOTTED WHITE LANE EXTENSION LINE - 6" (2' LINE & 6' GAP)
DYLEx		DOTTED YELLOW LANE EXTENSION LINE - 6" (2' LINE & 6' GAP)
BYL		BROKEN YELLOW LINE - 6"
DBYL		DOUBLE YELLOW LINE - 2 - 6" LINES
SYL		SOLID YELLOW LINE - 6"
SYGL		SOLID YELLOW GORE LINE 12" @ 45°, (SPACING NOTED)
 SCHOOL		SCHOOL ZONE - WHITE
		HANDICAP SYMBOL - WHITE
		PAVEMENT ARROW - WHITE
ONLY		LEGEND "ONLY" - WHITE

TRAFFIC SIGNAL SYMBOLS

EXISTING	PROPOSED	DESCRIPTION
		CONTROL CABINET GROUND MOUNTED WITH FOUNDATION
		CONTROL CABINET POLE MOUNTED
	 Ø2	CONTROLLER PHASE
	 MA-1	MAST ARM, SHAFT & BASE (ARM LENGTH AS NOTED)
		VEHICULAR SIGNAL HEAD (ALPHA-NUMERIC DESIGNATION AS NOTED)
		VEHICULAR SIGNAL HEAD, OPTICALLY PROGRAMMED
		VEHICULAR SIGNAL HEAD (REMOVED & RESET)
		FLASHING BEACON
		PEDESTRIAN SIGNAL HEAD
		PEDESTRIAN SIGNAL HEAD, OPTICALLY PROGRAMMED
 OHH		PULL BOX 12"x12" OR HANDHOLE
		LOOP DETECTOR
		PEDESTRIAN PUSH BUTTON, SIGN (DIRECTIONAL ARROW AS SHOWN) AND SADDLE
		PRE-EMPTION DETECTOR
		PRE-EMPTION CONFIRMATION STROBE
		SIGNAL CONDUIT (SINGLE RUN)
		SIGNAL CONDUIT (DOUBLE RUN)
		SIGNAL POST & BASE
	 M	MAGNETIC DETECTOR
		SCHOOL ZONE SPEED LIMIT SIGN
		MICROWAVE OR ULTRASONIC DETECTOR
		VIDEO DETECTION CAMERA
		VIDEO DETECTION ZONE

TRAFFIC SIGNAL SYSTEMS

R	STEADY CIRCULAR RED
Y	STEADY CIRCULAR AMBER
G	STEADY CIRCULAR GREEN
FR	FLASHING CIRCULAR RED
FY	FLASHING CIRCULAR AMBER
+FY	FLASHING YELLOW LEFT ARROW
R→	STEADY RED RIGHT ARROW
Y→	STEADY AMBER RIGHT ARROW
G→	STEADY GREEN RIGHT ARROW
+R	STEADY RED LEFT ARROW
+Y	STEADY AMBER LEFT ARROW
+G	STEADY GREEN LEFT ARROW
W	STEADY WALK (PERSON WALKING) - LUNAR WHITE
DW	STEADY DON'T WALK (HAND) - PORTLAND ORANGE
FDW	FLASHING DON'T WALK (FLASHING HAND) - PORTLAND ORANGE

ABBREVIATIONS		ABBREVIATIONS (cont.)	
GENERAL		GENERAL	
AADT	ANNUAL AVERAGE DAILY TRAFFIC	PROP	PROPOSED
ABAN	ABANDON	PSB	PLANTABLE SOIL BORROW
ADJ	ADJUST	PT	POINT OF TANGENCY
APPROX.	APPROXIMATE	PVC	POINT OF VERTICAL CURVATURE
A.C.	ASPHALT CONCRETE	PVI	POINT OF VERTICAL INTERSECTION
ACCM PIPE	ASPHALT COATED CORRUGATED METAL PIPE	PVT	POINT OF VERTICAL TANGENCY
BIT.	BITUMINOUS	PVMT	PAVEMENT
BC	BOTTOM OF CURB	PWW	PAVED WATER WAY
BD.	BOUND	R	RADIUS OF CURVATURE
BL	BASELINE	R&D	REMOVE AND DISPOSE
BLDG	BUILDING	RCP	REINFORCED CONCRETE PIPE
BM	BENCHMARK	RD	ROAD
BO	BY OTHERS	RDWY	ROADWAY
BOS	BOTTOM OF SLOPE	REM	REMOVE
BR.	BRIDGE	RET	RETAIN
CB	CATCH BASIN	RET WALL	RETAINING WALL
CBCI	CATCH BASIN WITH CURB INLET	ROW	RIGHT OF WAY
CC	CEMENT CONCRETE	RR	RAILROAD
CCM	CEMENT CONCRETE MASONRY	R&R	REMOVE AND RESET
CEM	CEMENT	R&S	REMOVE AND STACK
CI	CURB INLET	RT	RIGHT
CIP	CAST IRON PIPE	SB	STONE BOUND
CLF	CHAIN LINK FENCE	SHLD	SHOULDER
CL	CENTERLINE	S.I.P.	STAY-IN-PLACE
CMP	CORRUGATED METAL PIPE	SMH	SEWER MANHOLE
CSP	CORRUGATED STEEL PIPE	ST	STREET
CO.	COUNTY	STA	STATION
CONC	CONCRETE	SSD	STOPPING SIGHT DISTANCE
CONT	CONTINUOUS	SHLO	STATE HIGHWAY LAYOUT LINE
CONST	CONSTRUCTION	SW	SIDEWALK
CR GR	CROWN GRADE	T	TANGENT DISTANCE OF CURVE/TRUCK %
DHV	DESIGN HOURLY VOLUME	T&B	TOP AND BOTTOM
DI	DROP INLET	TAN	TANGENT
DIA	DIAMETER	TEMP	TEMPORARY
DIP	DUCTILE IRON PIPE	TC	TOP OF CURB
DW	STEADY DON'T WALK - PORTLAND ORANGE	TOS	TOP OF SLOPE
DWY	DRIVEWAY	TYP	TYPICAL
ELEV (or EL.)	ELEVATION	UP	UTILITY POLE
EMB	EMBANKMENT	VAR	VARIES
EOP	EDGE OF PAVEMENT	VERT	VERTICAL
EXIST (or EX)	EXISTING	VC	VERTICAL CURVE
EXC	EXCAVATION	WCR	WHEEL CHAIR RAMP
F&C	FRAME AND COVER	WG	WATER GATE
F&G	FRAME AND GRATE	WIP	WROUGHT IRON PIPE
FDN.	FOUNDATION	WM	WATER METER/WATER MAIN
FLDSTN	FIELDSTONE	X-SECT	CROSS SECTION
GAR	GARAGE		
GD	GROUND		
GG	GAS GATE		
GI	GUTTER INLET		
GIP	GALVANIZED IRON PIPE		
GRAN	GRANITE		
GRAV	GRAVEL		
GRD	GUARD		
HDW	HEADWALL		
HMA	HOT MIX ASPHALT		
HOR	HORIZONTAL		
HYD	HYDRANT		
INV	INVERT		
JCT	JUNCTION		
L	LENGTH OF CURVE		
LB	LEACH BASIN		
LP	LIGHT POLE		
LT	LEFT		
MAX	MAXIMUM		
MB	MAILBOX		
MH	MANHOLE		
MHB	MASSACHUSETTS HIGHWAY BOUND		
MIN	MINIMUM		
NIC	NOT IN CONTRACT		
NO.	NUMBER		
O.C.	ON CENTER		
PC	POINT OF CURVATURE		
PCC	POINT OF COMPOUND CURVATURE		
P.G.L.	PROFILE GRADE LINE		
PI	POINT OF INTERSECTION		
POC	POINT ON CURVE		
POT	POINT ON TANGENT		
PRC	POINT OF REVERSE CURVATURE		
PROJ	PROJECT		


TRAFFIC SIGNAL	
CAB.	CABINET
CCVE	CLOSED CIRCUIT VIDEO EQUIPMENT
DW	STEADY DON'T WALK
FDW	FLASHING DON'T WALK
FR	FLASHING CIRCULAR RED
FRL	FLASHING RED LEFT ARROW
FRR	FLASHING RED RIGHT ARROW
FY	FLASHING CIRCULAR AMBER
FYL	FLASHING AMBER LEFT ARROW
FYR	FLASHING AMBER RIGHT ARROW
G	STEADY CIRCULAR GREEN
GL	STEADY GREEN LEFT ARROW
GR	STEADY GREEN RIGHT ARROW
GSL	STEADY GREEN SLASH LEFT ARROW
GSR	STEADY GREEN SLASH RIGHT ARROW
GV	STEADY GREEN VERTICAL ARROW
OL	OVERLAP
PED	PEDESTRIAN
PTZ	PAN, TILE, ZOOM
R	STEADY CIRCULAR RED
RL	STEADY RED LEFT ARROW
RR	STEADY RED RIGHT ARROW
TR SIG	TRAFFIC SIGNAL
TSC	TRAFFIC SIGNAL CONDUIT
W	STEADY WALK
Y	STEADY CIRCULAR AMBER
YL	STEADY AMBER LEFT ARROW

O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 LEGEND.DWG (BETA STB BW STB)

					DRAWN BY:	REGISTERED PROFESSIONAL	PREPARED BY	SUBCONSULTANT	SCALE	TITLE	BETA JOB NO. 6182
					DESIGNED BY:					HIGH STREET STREETSCAPE CLINTON, MA	ISSUE DATE 7/16/2020
					CHECKED BY:					LEGEND & ABBREVIATIONS	SHEET NO. 2 OF 60
NUMBER	DATE	MADE BY	CHECKED BY		REVISIONS						

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 KEY PLAN.DWG (BETA STB BW.STB)



SHEET NUMBER LEGEND

- XX CONSTRUCTION PLAN
- XX CURB TIE & GRADING PLAN
- XX SIGN & PAVEMENT MARKING PLAN


NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NJM
DESIGNED BY:	NJM
CHECKED BY:	TJL

REGISTERED PROFESSIONAL  
  
For  
Review  
Only

PREPARED BY  
  
www.BETA-Inc.com

SUBCONSULTANT



TITLE

**HIGH STREET STREETSCAPE  
CLINTON, MA**

**KEY PLAN**

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	3 OF 60



1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION LAYOUT SURVEYS. THE CONTRACTOR SHALL EMPLOY A COMPETENT REGISTERED PROFESSIONAL SURVEYOR, REGISTERED IN THE COMMONWEALTH OF MASSACHUSETTS, TO COMPLETE ALL CONSTRUCTION LAYOUT.
2. THE ACCURACY AND COMPLETENESS OF ALL UNDERGROUND AND OVERHEAD UTILITIES AS SHOWN ON THE PLANS IS NOT GUARANTEED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE EXACT LOCATION, SIZE, TYPE, DEPTH, ETC. OF ALL UNDERGROUND UTILITIES THAT MAY BE AFFECTED BY THE WORK. ALL TOWN-OWNED UTILITY STRUCTURES, WITHIN AREAS AFFECTED BY THE WORK, SHALL BE ADJUSTED OR REMODELED TO NEW LINE AND GRADE AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS. ANY UTILITY AND/GUY POLES, WITHIN AREAS AFFECTED BY THE WORK, SHALL BE REMOVED AND RESET BY THE RESPECTIVE UTILITY COMPANY. ALTERATIONS TO UTILITIES AND UTILITY STRUCTURES NOT OWNED BY THE TOWN SHALL BE MADE BY THE RESPECTIVE UTILITY OWNERS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE WORK IN ADVANCE WITH THOSE UTILITY OWNERS.
3. ALL EXISTING DRAINAGE STRUCTURES SHALL BE RETAINED UNLESS OTHERWISE NOTED ON THE PLANS.
4. THE CONTRACTOR SHALL VERIFY EXISTING GRADES AT CRITICAL POINTS AND PROPOSED GRADES. IF ANY ADJUSTMENT IS REQUIRED DUE TO DIFFERENT GRADES FOUND IN THE FIELD, THE CONTRACTOR SHALL NOTIFY AND OBTAIN THE APPROVAL OF THE ENGINEER PRIOR TO PERFORMING THE WORK.
5. EROSION CONTROL DEVICES SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION, AND SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION AND SHALL BE REMOVED UPON COMPLETION OF ALL THE WORK WHEN ALL DISTURBED AREAS ARE STABILIZED, TO THE SATISFACTION OF THE ENGINEER.
6. ALL PROPOSED DRAINAGE STRUCTURES OR CASTINGS SHALL BE AS PER TOWN OF CLINTON STANDARDS UNLESS OTHERWISE NOTED.
7. WHEN A PROPOSED CATCH BASIN INTERFERES WITH ANY OTHER UNDERGROUND UTILITY, A GUTTER INLET SHALL BE USED, AS DIRECTED BY THE ENGINEER. ANY CHANGES TO DRAINAGE DESIGN DUE TO FIELD CONDITIONS SHALL BE VERIFIED AND APPROVED BY THE ENGINEER.
8. ANY EXISTING GRANITE CURB THAT CAN BE RE-USED SHALL BE R&R AS DIRECTED BY THE ENGINEER. NEW GRANITE CURB SHALL NOT BE INTERLAYERED WITH R&R GRANITE CURB. IF EXISTING CATCH BASINS ARE TO REMAIN IN PLACE WITH GRANITE CURB BEHIND THEM, THE CONTRACTOR SHALL REPLACE THE EXISTING CURB WITH A CURB INLET SECTION, AS DIRECTED BY THE ENGINEER.
9. ALL TREES WITHIN THE LIMITS OF WORK SHALL BE RETAINED UNLESS OTHERWISE NOTED ON THE PLANS. HOWEVER, SOME TREES, IN CRITICAL LOCATIONS, ARE NOTED TO BE RETAINED, FOR CLARITY. THE ENGINEER SHALL OBTAIN THE APPROVAL OF THE TOWN TREE WARDEN OR HIS EQUIVALENT OFFICER BEFORE ANY TREE IS REMOVED.
10. TREES AND FOLIAGE TO BE RETAINED, WHICH RESTRICT SIGHT DISTANCE OR RESTRICT HORIZONTAL OR VERTICAL CLEARANCES SHALL BE TRIMMED AS DIRECTED BY THE ENGINEER.
11. UNLESS OTHERWISE NOTED, ALL EXISTING WALLS WITHIN THE PROJECT LIMITS SHALL BE RETAINED.
12. WHEN WORKING NEXT TO EXISTING TREES, WALLS, BUILDINGS, VAULTS OR FENCES, THE CONTRACTOR SHALL EXERCISE EXTREME CAUTION NOT TO DISTURB THE EXISTING WALLS, TREES BUILDINGS, VAULTS OR FENCES. IF THE CONTRACTOR DOES DAMAGE ANY EXISTING TREES, WALLS, BUILDINGS, VAULTS OR FENCES AS A RESULT OF THE CONSTRUCTION PROCESS, IT SHALL BE HIS/HER RESPONSIBILITY (THE CONTRACTOR) TO REPAIR ALL DAMAGES AS DIRECTED BY THE ENGINEER. ALL WORK ASSOCIATED WITH THE REPAIR OR REPLACEMENT OF EXISTING TREES, WALLS OR FENCES SHALL BE CONSIDERED AS INCLUDED IN THE BID PRICE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED THEREFORE.
13. IN AREAS OF NEW SIDEWALK, NEW EDGE OF PAVEMENT OR CURB WITHOUT SIDEWALK, OR ANY WORK ADJACENT TO EXISTING GRASS AREAS, LOAM AND SEED SHALL BE PROVIDED AS NECESSARY TO REPAIR ANY DAMAGE TO THE GRADE CAUSED BY THE CONSTRUCTION PROCESS, AS DIRECTED BY THE ENGINEER.
14. ALL AREAS OUTSIDE THE LIMITS OF THE PROPOSED WORK THAT HAVE BEEN DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY THE CONTRACTOR TO THEIR ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE, TO THE SATISFACTION OF THE ENGINEER AND THE PROPERTY OWNER.
15. JOINTS BETWEEN NEW HOT MIX ASPHALT (HMA) ROADWAY PAVEMENT AND SAW-CUT EXISTING PAVEMENT SHALL BE SEALED WITH BITUMEN AND BACKSANDED. SAWCUTTING WILL BE PERFORMED BY MECHANICAL MEANS.
16. MAILBOXES, FENCES, ETC., THAT NEED TO BE RELOCATED SHALL BE REMOVED AND RESET (R&R) IN THEIR NEW LOCATIONS AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. THE OWNER SHALL BE CONSULTED PRIOR TO THE WORK. ALL FENCES AND HEDGES SHALL BE RETAINED AS NOTED ON THE PLANS OR AS DIRECTED BY THE ENGINEER.
17. EXISTING ON-THE-GROUND SURVEY BY LIGHTHOUSE LAND SURVEYING, LLC, 75 KIMBERLY ROAD, TAUNTON, MA, IN AUGUST AND SEPTEMBER 2019.


18. PROPOSED BOUNDS, AND BOUNDS REMOVED AND RESET SHALL BE SET FLUSH WITH THE ADJACENT WALK SURFACE


1. ALL WHEELCHAIR RAMPS SHALL CONFORM TO THE REQUIREMENTS OF THE ARCHITECTURAL ACCESS BOARD (A.A.B.), THE AMERICANS WITH DISABILITIES ACT (A.D.A.) AND MASSDOT HIGHWAY DIVISION.
2. ALL PROPOSED CURB FOR WHEELCHAIR RAMP TRANSITIONS SHALL BE CUT AND TRANSITIONED AS NECESSARY TO PROVIDE THE CORRECT TRANSITION LENGTHS FOR EACH WHEELCHAIR RAMP, AS SHOWN ON THE WHEELCHAIR RAMP DETAILS OR AS DIRECTED BY THE ENGINEER. ANY EXISTING CURB INLETS, IN AREAS OF NEW WHEELCHAIR RAMP TRANSITIONS, SHALL BE REMOVED AND REPLACED WITH APPROPRIATE TRANSITION CURB, AS DIRECTED BY THE ENGINEER.
3. IN NO CASE, EXCEPT MAXIMUM LENGTH HIGH SIDE TRANSITIONS, SHALL ANY TRANSITION SLOPE OF ANY WHEELCHAIR RAMP EXCEED 7.5%. PROPOSED WHEELCHAIR RAMP SLOPES, ESPECIALLY HIGH SIDE TRANSITIONS, SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO THE POURING OF CONCRETE, AND ADJUSTED, IF NECESSARY, AT THE DIRECTION OF THE ENGINEER.
4. IN INSTANCES WHERE AN EXISTING MANHOLE, HANDHOLE OR OTHER "SURFACE" TYPE STRUCTURE THAT CANNOT BE REMOVED OR RESET, IS WITHIN THE WHEELCHAIR RAMP PATH OF TRAVEL, THE STRUCTURE SHALL BE CAREFULLY ADJUSTED SUCH THAT THE TOPMOST SURFACES OF THE STRUCTURE COVER SHALL BE FLUSH WITH THE RAMP SURFACE AND SHALL MATCH THE SLOPE OF THE NEW WHEELCHAIR RAMP EXACTLY, AS DIRECTED BY THE ENGINEER.
5. ANY UTILITY STRUCTURES WITHIN THE TRANSITIONS OF THE WHEELCHAIR RAMP TRANSITIONS SHALL ALSO BE ADJUSTED TO THE PROPOSED GRADE AND THE SLOPE OF THE SURFACE OF THE PROPOSED TRANSITION PANEL OR PANELS.
6. THE LOCATION OF PROPOSED WHEELCHAIR RAMPS ARE SHOWN ON THE CONSTRUCTION PLANS AND THE WHEELCHAIR RAMP DATA SCHEDULE. EXACT LOCATIONS MAY BE ADJUSTED, IF NECESSARY, BY THE ENGINEER IN THE FIELD.
7. DETECTABLE WARNING PANELS SHALL BE INSTALLED ON ALL WHEELCHAIR RAMPS IN ACCORDANCE WITH MASSDOT CONSTRUCTION STANDARD E 107.6.5 (2017) AND WILL BE PAID FOR UNDER ITEM 701.2.
8. PROPOSED WHEELCHAIR RAMP SLOPES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO THE POURING OF CONCRETE, AND ADJUSTED, IF NECESSARY, TO CONFORM TO THE LATEST STANDARDS, AS DIRECTED BY THE ENGINEER.
9. L: LENGTH OF WCR AND DWY TRANSITION TO BE VERIFIED IN FIELD BY CONTRACTOR. SEE TABLE 1 ON THIS SHEET FOR TRANSITION LENGTH REFERENCES. ADA COMPLIANCE SHALL BE MET IN ALL INSTANCES.



## WHEELCHAIR RAMP AND DRIVEWAY HIGH SIDE TRANSITION LENGTHS


NOTE:  
SPECIFIED TRANSITION LENGTHS  
FOR APPLICABLE WHEELCHAIR  
RAMPS CAN APPLY TO BOTH LEFT  
AND RIGHT SIDES.




					DRAWN BY: NJM	REGISTERED PROFESSIONAL   www.BETA-inc.com	PREPARED BY:	SUBCONSULTANT	SCALE  AS SHOWN  <small>UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION</small>	TITLE  <b>HIGH STREET STREETScape CLINTON, MA</b>  <b>CONSTRUCTION DETAILS</b>	BETA JOB NO. <u>6182</u>
					DESIGNED BY: CJT		ISSUE DATE <u>7/16/2020</u>				
					CHECKED BY: TJL		SHEET NO. <u>4 OF 60</u>				
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS							




016100516182 - CLINTON - HIGH ST STREETSCAPE DRAWING FILES\PLANSET\16182 CONSTRUCTION DETAILS.DWG (BETA STB BW STB)




WHEELCHAIR RAMP #25 STA 18+11.0' RT  
NOT TO SCALE




WHEELCHAIR RAMP #26 STA 18+20.0' LT  
WHEELCHAIR RAMP #27 STA 18+34.6' LT  
NOT TO SCALE




WHEELCHAIR RAMP #29 STA 303+55.40' LT (CHURCH ST WEST)  
NOT TO SCALE




WHEELCHAIR RAMP DETAIL "A"  
NOT TO SCALE



WHEELCHAIR RAMP DETAIL TYPE "B"  
NOT TO SCALE



WHEELCHAIR RAMP TYPE "C"  
NOT TO SCALE



WHEELCHAIR RAMP STA 12+22.9' RT  
NOT TO SCALE

WHEELCHAIR RAMP DATA							
WCR NO.	ALIGNMENT	STATION AND OFFSET	OPENING WIDTH AT GUTTER	RAMP LENGTH	CURB REVEAL AT RAMP / TRANSITION LIMITS (IN)		TYPE
					LT	RT	
1	UNION STREET	111+18.0' 22.8' LT	8.1'	8.3' - 8.4'	6" R	6" R	A
2	UNION STREET	111+17.0' 20.4' RT	6.5'	8.0' - 11.4'	6" R	6" R	A
3	HIGH STREET	00+32.8' 18.8' RT	6.5'	8.0' - 11.2'	6" R	6" R	A
4	HIGH STREET	00+39.8' 30.0' LT	6.5'	8.0' - 9.8'	6" R	6" R	A
INTENTIONALLY LEFT BLANK							
6	HIGH STREET	02+68.5' 18.5' RT	5.5'	5.5'	4" R	4" R	A
7	HIGH STREET	02+69.4' 20.6' LT	6.5'	5.4' - 5.5'	4" R	4" R	A
8	HIGH STREET	03+39.9' 23.4' LT	5.5'	5.5'	6" R	6" R	A
9	HIGH STREET	04+61.7' 14.5' LT	6.5'	6.0'	4" R	4" R	A
10	HIGH STREET	04+60.6' 19.8' RT	6.5'	6.0' - 8.3'	4" R	4" R	A
11	CHURCH ST (WEST)	300+18.8' 19.5' LT	6.5'	6.0' - 12.6'	4" R	6" R	A
12	CHURCH ST (EAST)	204+15.3' 28.1' LT	6.5'	6.0' - 10.0'	4" R	6" R	A
13	CHURCH ST (EAST)	204+23.2' 18.9' RT	6.5'	7.0' - 9.7'	6" R	6" R	A
14	CHURCH ST (WEST)	300+34.7' 28.5' LT	6.5'	6.0' - 11.1'	4" R	4" R	A
15	HIGH STREET	05+51.2' 14.7' LT	6.5'	6.0' - 8.0'	4" R	4" R	A
16	HIGH STREET	05+49.9' 19.2' RT	6.5'	7.0'	5" R	5" R	A
17	HIGH STREET	05+62.7' 22.5' LT	5.5'	6.0'	4" R	4" R	A
INTENTIONALLY LEFT BLANK							
19	HIGH STREET	09+30.7' 19.5' RT	6.5'	8.0'	4" R	4" R	A
20	HIGH STREET	09+31.7' 19.8' LT	6.5'	8.0'	4" R	4" R	A
21	HIGH STREET	12+22.9' 31.0' RT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL
22	HIGH STREET	12+57.4' 30.6' RT	6.5'	8.3' - 8.7'	6" R	6" R	A
23	HIGH STREET	12+68.9' 15.3 LT	6.5'	8.5'	4" R	4" R	A
24	HIGH STREET	12+69.2' 18.7' RT	6.5'	8.5'	6" R	6" R	A
25	HIGH STREET	18+11.0' 27.4' RT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL
26	HIGH STREET	18+20.0' 27.5' LT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL
27	HIGH STREET	18+34.6' 42.7' LT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL
28	CHURCH ST (EAST)	200+21.0' 21.4' RT	5.0'	7.0'	6" R	6" R	C
29	CHURCH ST (WEST)	303+55.4' 21.5' LT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL
30	CHURCH ST (WEST)	303+58.9' 20.3' RT	5.0'	7.7' - 7.9'	6" R	4" R	B

\* TOLERANCE FOR CONSTRUCTION ±0.5%

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS	

DRAWN BY:	NJM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL

PREPARED BY



SUBCONSULTANT

SCALE

AS SHOWN

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

HIGH STREET STREETSCAPE  
CLINTON, MA  
  
CONSTRUCTION DETAILS


BETA JOB NO. 6182

ISSUE DATE 7/16/2020


SHEET NO. 5 OF 60




0:\6\05\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 CONSTRUCTION DETAILS.DWG (BETA STB BW STB)




DETAIL FOR DWY-1  
NOT TO SCALE




DETAIL FOR DRIVEWAY TYPE "A"  
NOT TO SCALE




DETAIL SECTION FOR DRIVEWAY TYPES "A" AND "B"  
NOT TO SCALE




DETAIL SECTION FOR DRIVEWAY TYPE "C"  
NOT TO SCALE



DETAIL FOR DRIVEWAY TYPE "B"  
(WITH WCR TYPE A ADJACENT RIGHT OR LEFT SIDE  
OF DRIVEWAY)  
NOT TO SCALE



DETAIL FOR DRIVEWAY TYPE "C"  
NOT TO SCALE



DETAIL FOR DRIVEWAY TYPE "D"  
NOT TO SCALE

\* TOLERANCE FOR CONSTRUCTION ±0.5%

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NUM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL	PREPARED BY



SUBCONSULTANT


SCALE
AS SHOWN
UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE
HIGH STREET STREETSCAPE CLINTON, MA
CONSTRUCTION DETAILS



BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	6 OF 60




0:\6\005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 CONSTRUCTION DETAILS.DWG (BETA STB BW STB)




DETAIL FOR DWY-10, DWY-11, DWY-12, DWY-13  
NOT TO SCALE




DETAIL FOR DWY-14  
NOT TO SCALE



CEMENT CONCRETE RAMP & HANDRAIL DETAIL (STA 0+67± TO STA 1+05±)  
NOT TO SCALE



TREE PROTECTION - EXISTING TREE(S)  
NOT TO SCALE



DRIVEWAY OPENING DATA																
DWY NO.	ALIGNMENT	STATION AND OFFSET	OPENING WIDTH AT GUTTER	APRON LENGTH	CURB REVEAL AT RAMP / TRANSITION LIMITS (IN)		TYPE		DWY NO.	ALIGNMENT	STATION AND OFFSET	OPENING WIDTH AT GUTTER	APRON LENGTH	CURB REVEAL AT RAMP / TRANSITION LIMITS (IN)		TYPE
					LT	RT								LT	RT	
1	HIGH STREET	02+49.1' 25.4' LT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL		15	HIGH STREET	15+84.1' 25.0' RT	17.5'	3.0'	6.0"	6.0"	A
2	HIGH STREET	06+44.4' 28.0' RT	24.1'	3.0'	6.0"	6.0"	A		16	HIGH STREET	16+51.7' 24.8' RT	24.5'	3.0'	6.0"	6.0"	A
3	HIGH STREET	07+67.7' 27.6' RT	22.0'	3.0'	6.0"	6.0"	A		17	HIGH STREET	17+16.1' 24.5' LT	28.0'	-	6.0"	6.0"	C
4	HIGH STREET	09+09.9' 27.7' RT	27.0'	3.0'	6.0"	6.0"	B		18	HIGH STREET	17+53.9' 24.7' LT	31.0'	3.0'	6.0"	6.0"	A
5	HIGH STREET	09+50.1' 27.8' LT	19.9'	3.0'	4.0"	4.0"	B		19	CHURCH ST (EAST)	200+73.4' 20.9' LT	25.5'	3.0'	6.0"	6.0"	D
6	HIGH STREET	09+65.1' 27.6' RT	54.5'	3.0'	4.0"	6.0"	B		20	CHURCH ST (EAST)	201+65.7' 20.5' LT	61.0'	3.0'	6.0"	6.0"	D
7	HIGH STREET	10+76.6' 28.1' RT	20.5'	3.0'	6.0"	6.0"	A		21	CHURCH ST (EAST)	202+70.2' 18.6' RT	14.5'	4.0'	5.0"	6.0"	A
8	HIGH STREET	11+23.40' 27.7' LT	22.0'	3.0'	6.0"	6.0"	A		22	CHURCH ST (EAST)	203+40.2' 18.4' RT	45.4'	-	6.0"	6.0"	C
9	HIGH STREET	12+88.79' 25.5' LT	22.0'	3.0'	4.0"	6.0"	B		23	CHURCH ST (WEST)	301+36.3' 20.8' LT	16.8'	3.0'	6.0"	6.0"	A
10	HIGH STREET	13+65.6' 26.0' RT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL		24	CHURCH ST (WEST)	301+70.7' 20.5' RT	18.5'	3.0'	6.0"	6.0"	A
11	HIGH STREET	14+11.4' 25.6' RT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL		25	CHURCH ST (WEST)	302+31.6' 20.9' LT	15.7'	3.0'	3.0"	6.0"	A
12	HIGH STREET	14+52.8' 25.5' RT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL		26	CHURCH ST (WEST)	302+58.1' 20.7' RT	32.5'	-	6.0"	6.0"	C
13	HIGH STREET	14+96.6' 25.3' RT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL		27	CHURCH ST (WEST)	303+26.4' 20.6' RT	30.0'	-	4.0"	6.0"	C
14	HIGH STREET	15+08.9' 26.2' LT	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL	SEE DETAIL		28	CHURCH ST (EAST)	203+02.7' 21.7' LT	19.6'	-	4.0"	4.0"	C

\* TOLERANCE FOR CONSTRUCTION ±0.5%

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	REGISTERED PROFESSIONAL	PREPARED BY
NJM		
DESIGNED BY:		
CJT		
CHECKED BY:		
TJL		



SUBCONSULTANT


SCALE
AS SHOWN
UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE
HIGH STREET STREETSCAPE CLINTON, MA
CONSTRUCTION DETAILS


BETA JOB NO. 6182
ISSUE DATE 7/16/2020
SHEET NO. 7 OF 60



0:\6\05\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 CONSTRUCTION DETAILS.DWG (BETA STB BW.STB)



DETAIL FOR HYDRANT REMOVED AND RESET  
NOT TO SCALE




PRECAST CONCRETE CATCH BASIN (FLAT TOP SECTION)  
NOT TO SCALE


NOTE:

SEE MASSDOT 2017 CONSTRUCTION DETAILS E 201.4.0, E 202.4.0, and E 204.2.0 FOR PRECAST CATCH BASIN WITH CONCENTRIC CONE TOP PRECAST MANHOLE WITH CONCENTRIC CONE TOP AND GUTTER INLET RESPECTIVELY.

ALTERNATE MANHOLE OR CB ECCENTRIC CONE TOP SECTION



ALTERNATE MANHOLE TOP SLAB  
NOT TO SCALE




NOTES:


1. LENGTH AND WIDTH OF POLYPROPYLENE FABRIC MUST EXCEED EXISTING CATCH BASIN FRAME DIMENSIONS BY A MINIMUM OF 8".
2. REMOVE CATCH BASIN GRATE AND INSTALL POLYPROPYLENE FABRIC OVER CATCH BASIN FRAME. REPLACE CATCH BASIN GRATE TO SECURE POLYPROPYLENE FABRIC IN PLACE.
3. FOR USE ON ALL EXISTING CATCH BASINS THAT ARE IN OPERATION DURING CONSTRUCTION.

SILT SACK


NOT TO SCALE




CONTINGENCY DETAIL FOR STORM  
DRAIN LATERAL LINES  
(USE ONLY IF OBSTRUCTION IS ENCOUNTERED)  
NOT TO SCALE



TRAFFIC SIGN



UTILITY POLE



HYDRANT

DETAIL FOR MINIMUM OFFSET DISTANCES  
FOR SIDEWALK OBSTRUCTIONS  
NOT TO SCALE

NOTES:

1. THE CONTRACTOR SHALL VERIFY THE LOCATION AND CLEARANCE OF ALL OBJECTS (SIGNS, POLES ETC.) (OBSTRUCTIONS) TO BE SET WITHIN THE PROPOSED SIDEWALK, PRIOR TO FINAL PAVING, AND SHALL ENSURE THAT A MINIMUM CLEAR PATH-OF-TRAVEL OF 36 INCHES IS MAINTAINED. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY LOCATION WHICH CANNOT MEET THE CLEARANCE REQUIREMENTS.
2. MINIMUM CLEAR PATH ON ALL SIDEWALKS SHALL BE 36 INCHES, EXCLUDING THE CURB.
3. CONTRACTOR TO ATTAIN 60" CLEAR (INCLUDING CURB) WHERE FEASIBLE. ADVISE ENGINEER WHEN 60" IS NOT AVAILABLE.

\* TOLERANCE FOR CONSTRUCTION ±0.5%

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NJM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL	PREPARED BY

 www.BETA-Inc.com
-----------------------------------------------------------------------------------------------------------







SUBCONSULTANT

SCALE
AS SHOWN

TITLE
HIGH STREET STREETSCAPE CLINTON, MA
CONSTRUCTION DETAILS

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	8 OF 60





VAULT NOTES:


CONCRETE:  $f_c$  4000 PSI,  $\frac{3}{4}$  IN., 610 CEMENT CONCRETE

REINFORCING STEEL: ASTM A615 GRADE 60 EPOXY COATED

STEEL: ASTM A992 GRADE 50 HOT DIPPED GALVANIZED (U.O.N.)




DENOTES AREA TO BE REMOVED AND DISPOSED.

1. DIMENSIONS ARE NOT GUARANTEED. CONTRACTOR SHALL TAKE THEIR OWN MEASUREMENTS PRIOR TO STARTING CONSTRUCTION.
2. THE EXACT DEPTH OF DEMOLITION SHALL BE AS REQUIRED TO ACCOMMODATE THE PROPOSED SLAB THICKNESSES AND BEAM DEPTH. THE CONTRACTOR SHALL FINALIZE THESE DEPTHS ONCE THE EXISTING SLAB THICKNESS HAS BEEN DETERMINED DURING CONSTRUCTION.
3. TOP OF TOP FLANGE OF BEAMS SHALL BE MASKED WITH EPOXY PAINT PRIOR TO GALVANIZING AND PAINTED WITH A LIGHT RUST PREVENTATIVE COAT OF PRIMER AFTER GALVANIZING.

					DRAWN BY: DW	REGISTERED PROFESSIONAL <div style="text-align: center;"> <b>For Review Only</b> </div>	PREPARED BY  <a href="http://www.BETA-Inc.com">www.BETA-Inc.com</a>	SUBCONSULTANT	SCALE  AS SHOWN  <small>LINE ESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION</small>	TITLE  <div style="text-align: center;"> <b>HIGH STREET STREETScape CLINTON, MA</b>   <b>CONSTRUCTION DETAILS</b> </div>	BETA JOB NO. <u>6182</u>
					DESIGNED BY: DW						ISSUE DATE <u>7/16/2020</u>
					CHECKED BY: CWJ						SHEET NO. <u>OF 60</u>
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS							



7/16/2020 10:48 AM O:\6105\6182 - CLINTON - HIGH ST. STREETSCAPE\DRAWING FILES\PLANSET\6182 TYPICAL SECTIONS.DWG (BETA STD BW.STB)



**PAVEMENT NOTES**

**PROPOSED PAVEMENT MILLING AND OVERLAY**

SURFACE COURSE: 1-1/2" SUPERPAVE SURFACE COURSE 9.5 (SSC-9.5) OVER ASPHALT EMULSION FOR TACK COAT OVER

PAVEMENT MILLING: 1-1/2" PAVEMENT MICROMILLING

**PROPOSED FULL DEPTH CONSTRUCTION**

SURFACE COURSE: 1-1/2" SUPERPAVE SURFACE COURSE 9.5 (SSC-9.5) OVER ASPHALT EMULSION FOR TACK COAT OVER

INTERMEDIATE COURSE: 2" SUPERPAVE INTERMEDIATE COURSE 12.5 (SIC-12.5) OVER ASPHALT EMULSION FOR TACK COAT OVER

BASE COURSE: 4" SUPERPAVE BASE COURSE 37.5 (SBC-37.5) OVER

SUB-BASE: 4" DENSE GRADED CRUSHED STONE FOR SUB BASE OVER 8" GRAVEL BORROW, TYPE b (MIN), AS REQUIRED

**PROPOSED CEMENT CONCRETE SIDEWALK, WHEELCHAIR RAMPS AND WALKS**

SURFACE: 4" CEMENT CONCRETE WALK SURFACE 4000 PSI, 3/4", 610 OVER

FOUNDATION: 8" GRAVEL BORROW, TYPE b, AS REQUIRED

**PROPOSED CEMENT CONCRETE DRIVEWAY AND SIDEWALK AT DRIVEWAY**

SURFACE: 6" CEMENT CONCRETE (AIR ENTRAINED 4000 PSI, 3/4", 610)

BASE COURSE: 8" GRAVEL BORROW, TYPE b, AS REQUIRED

**PROPOSED HMA DRIVEWAYS**

SURFACE: 1-1/2" SUPERPAVE SURFACE COURSE 9.5 (SSC-9.5) OVER 2" SUPERPAVE INTERMEDIATE COURSE 12.5 (SIC-12.5) OVER

FOUNDATION: 8" GRAVEL BORROW, TYPE b, AS REQUIRED

**PROJECT TACK COAT NOTES**

TACK COAT: ASPHALT EMULSION FOR TACK COAT, GRADE RS-1 SHALL BE PLACED AT A RATE OF:  
0.07 GALLONS PER SQUARE YARD OVER MILLED SURFACES  
0.07 GALLONS PER SQUARE YARD OVER CEMENT CONCRETE BASE COURSE  
0.05 GALLONS PER SQUARE YARD OVER SMOOTH TIGHT PAVEMENTS PRIOR TO PAVING AN OVERLAY

ASPHALT SEALANT: (ITEM 490.1) ASPHALT RUBBER SHALL BE APPLIED TO THE EDGES AND SEAMS OF NEW PAVEMENT AND AS DIRECTED BY THE ENGINEER

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS	

DRAWN BY:  
NJM  
DESIGNED BY:  
NJM  
CHECKED BY:  
TJL

REGISTERED PROFESSIONAL  
For Review Only



SUBCONSULTANT

SCALE

NONE

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

**HIGH STREET STREETSCAPE  
CLINTON, MA**

**TYPICAL SECTIONS**



BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 10 OF 60




7/16/2020 10:48 AM O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 TYPICAL SECTIONS.DWG (BETA STB BW STB)



					DRAWN BY: NJM	REGISTERED PROFESSIONAL	PREPARED BY	SUBCONSULTANT	SCALE	TITLE	BETA JOB NO. 6182
					DESIGNED BY: NJM				NONE	HIGH STREET STREETSCAPE CLINTON, MA	ISSUE DATE 7/16/2020
					CHECKED BY: TJL					TYPICAL SECTIONS	SHEET NO. 11 OF 60
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS					UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION		



- NOTES:
- ALL SURFACE FEATURES INCLUDING BUT NOT LIMITED TO TREES, WALLS, LANDSCAPING FEATURES, HARDSCAPES, SHRUBS, FENCES, STEPS, DOORWAYS, MAILBOXES, TRASH CANS, BENCHES, WALKS, ETC., SHALL BE RETAINED UNLESS OTHERWISE NOTED.
  - PROPOSED BACK OF SIDEWALK SHALL GENERALLY MEET EXISTING BACK OF SIDEWALK LOCATION UNLESS OTHERWISE SHOWN ON THE PLANS. SIDEWALK WIDTH VARIES.



O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 CONSTRUCTION PLAN (2020).DWG (BETA STB BWI.STB)


NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NJM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL	PREPARED BY
-------------------------	-------------



SUBCONSULTANT
---------------




TITLE
HIGH STREET STREETSCAPE CLINTON, MA
CONSTRUCTION PLAN

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	12 OF 60



O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 CONSTRUCTION PLAN (2020) DWG (BETA STB BW) STB



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:  
NJM  
DESIGNED BY:  
CJT  
CHECKED BY:  
TJL

REGISTERED PROFESSIONAL

PREPARED BY



SUBCONSULTANT

SCALE



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

HIGH STREET STREETSCAPE  
CLINTON, MA  
CONSTRUCTION PLAN

BETA JOB NO. 6182



ISSUE DATE 7/16/2020

SHEET NO. 13 OF 60









O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 CONSTRUCTION PLAN (2020).DWG (BETA STB BW STB)

					DRAWN BY: NUM	REGISTERED PROFESSIONAL	PREPARED BY	SUBCONSULTANT	SCALE  SCALE IN FEET: 1"=20'	TITLE <b>HIGH STREET STREETSCAPE CLINTON, MA  CONSTRUCTION PLAN</b>	BETA JOB NO. 6182
					DESIGNED BY: CJT						ISSUE DATE 7/16/2020
					CHECKED BY: TJL						SHEET NO. 15 OF 60
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS							



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION












0161005					
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS	

REGISTERED PROFESSIONAL


SUBCONSULTANT	



O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLAN\SET\6182 CURB TIE AND BASELINE PLAN.DWG (BETA STB BW STB)



CURVE TABLE				
CURVE #	LENGTH	DELTA	RADIUS	TANGENT
C25	6.28	89.91	4.00	3.99
C22	6.28	89.90	4.00	3.99
C19	5.97	68.43	5.00	3.40
C20	43.24	82.57	30.00	26.34
C17	3.97	44.92	5.06	2.09
C16	42.31	80.80	30.00	25.53
C13	4.25	48.67	5.00	2.26
C21	6.94	79.57	5.00	4.16
C14	9.30	35.52	15.00	4.80
C18	27.60	79.06	20.00	16.51
C23	6.30	90.23	4.00	4.02
C24	6.28	90.00	4.00	4.00



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NJM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL

PREPARED BY



SUBCONSULTANT

SCALE



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

HIGH STREET STREETSCAPE  
CLINTON, MA

CURB TIE AND BASELINE PLAN


BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 19 OF 60



O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 CURB TIE AND BASELINE PLAN.DWG (BETA STB BW STB)




NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NJM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL	PREPARED BY




SUBCONSULTANT




TITLE	HIGH STREET STREETSCAPE CLINTON, MA
TITLE	CURB TIE AND BASELINE PLAN
BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	20 OF 60





CURVE TABLE				
CURVE #	LENGTH	DELTA	RADIUS	TANGENT
C39	10.21	23.64	24.75	5.18
C40	18.02	34.42	30.00	9.29



O:\61005\6182 - CLINTON - HIGH ST STREETScape\DRAWING FILES\PLAN\SET\6182 CURB TIE AND BASELINE PLANDWG (BETA STB BW STB)

				DRAWN BY: NJM	REGISTERED PROFESSIONAL	PREPARED BY	SUBCONSULTANT	SCALE  SCALE IN FEET: 1"=20'	TITLE <b>HIGH STREET STREETScape CLINTON, MA</b>  <b>CURB TIE AND BASELINE PLAN</b>	BETA JOB NO. 6182
				DESIGNED BY: CJT	 www.BETA-Inc.com					ISSUE DATE 7/16/2020
				CHECKED BY: TJL						SHEET NO. 21 OF 60
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS						

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION













7/16/2020 10:50 AM O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 PROFILE.DWG (BETA STB BW.STB)





					DRAWN BY: NJM	REGISTERED PROFESSIONAL	PREPARED BY	SUBCONSULTANT	SCALE HOR. SCALE IN FEET: 1"=20' VER. SCALE IN FEET: 1"=4'	TITLE HIGH STREET STREETSCAPE CLINTON, MA PROFILE - HIGH STREET	BETA JOB NO. 6182
					DESIGNED BY: CJT						ISSUE DATE 7/16/2020
					CHECKED BY: TJL						SHEET NO. 24 OF 60
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS							




7/16/2020 10:51 AM O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 PROFILE.DWG (BETA STB BW STB)




					DRAWN BY: NJM	REGISTERED PROFESSIONAL	PREPARED BY  www.BETA-Inc.com	SUBCONSULTANT	SCALE  HOR. SCALE IN FEET: 1"=20"  VER. SCALE IN FEET: 1"=4'  UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION	TITLE  HIGH STREET STREETSCAPE CLINTON, MA  PROFILE - HIGH STREET	BETA JOB NO. 6182
					DESIGNED BY: CJT						ISSUE DATE 7/16/2020
					CHECKED BY: TJL						SHEET NO. 25 OF 60
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS							




7/16/2020 10:51 AM O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 PROFILE.DWG (BETA STB BW STB)



					DRAWN BY: NJM	REGISTERED PROFESSIONAL	PREPARED BY	SUBCONSULTANT	SCALE	TITLE	BETA JOB NO. 6182				
					DESIGNED BY: CJT	 www.BETA-Inc.com			<div><div>HOR. SCALE IN FEET: 1"=20'</div><div><div><div>20</div><div>0</div><div>20</div><div>40</div></div><div><div>4</div><div>0</div><div>4</div><div>8</div></div></div><div>VER. SCALE IN FEET: 1"=4'</div></div>	<div><div>HIGH STREET STREETSCAPE CLINTON, MA</div><div>PROFILE - HIGH STREET</div></div>	ISSUE DATE 7/16/2020				
				CHECKED BY: TJL											SHEET NO. 26 OF 60
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS											



7/16/2020 10:51 AM O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 PROFILE.DWG (BETA STB BW.STB)



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	REGISTERED PROFESSIONAL
NUM	
DESIGNED BY:	
CJT	
CHECKED BY:	
TJL	

PREPARED BY

  
www.BETA-Inc.com

SUBCONSULTANT
---------------

SCALE

HOR. SCALE IN FEET: 1"=20'

VER. SCALE IN FEET: 1"=4'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE


**HIGH STREET STREETSCAPE  
CLINTON, MA**

**PROFILE - CHURCH STREET WEST**

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	27 OF 60



7/16/2020 10:52 AM O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 PROFILE.DWG (BETA STB BW.STB)



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NUM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL

PREPARED BY




www.BETA-Inc.com

SUBCONSULTANT

SCALE

HOR. SCALE IN FEET: 1"=20'



VER. SCALE IN FEET: 1"=4'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

**HIGH STREET STREETSCAPE  
CLINTON, MA**

**PROFILE - CHURCH STREET EAST**

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	28 OF 60



O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 GRADING PLAN.DWG (BETA STB BW.STB)

LEGEND

XXX.XX	PROP. ROADWAY GRADE
XXX.XX	PROP. TOP OF CURB/ SURFACE OF SIDEWALK GRADE. 6" TYPICAL REVEAL WHERE TOP OF CURB ELEVATION NOT PROVIDED
(XXX.XX)	MEET EXISTING GRADE
X" R	CURB REVEAL

NOTES:

- ON HIGH STREET AND CHURCH STREET, THE CONTRACTOR SHALL USE EXTREME CARE TO MATCH EXISTING BACK OF SIDEWALK ELEVATIONS AT BOTH SIDES OF ALL STEPS, WALKS, DRIVEWAYS, DOORWAYS AND OTHER CONTROL POINTS, UNLESS OTHERWISE NOTED ON THE PLANS. PRIOR TO ANY CONSTRUCTION, THE CONTRACTOR SHALL FIELD WALK THE PROJECT WITH THE ENGINEER TO VERIFY REQUIREMENTS AT ALL CONTROL POINTS.
- ALL CURB REVEAL TO TYPICALLY BE 6" UNLESS OTHERWISE SHOWN.
- ALL SIDEWALK TO TYPICALLY HAVE 1.5% CROSS SLOPE UNLESS OTHERWISE SHOWN.
- BRICK AND LANDSCAPED STRIPS HAVE VARYING CROSS SLOPE, WITH POSITIVE DRAINAGE TO THE ROADWAY.
- CONTRACTOR TO VERIFY POSITIVE DRAINAGE TO CB, GRADE AS REQUIRED.
- ANY CHANGES TO GRADING PLAN BY THE CONTRACTOR SHALL BE VERIFIED BY THE ENGINEER.




NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NJM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL	PREPARED BY
-------------------------	-------------



SUBCONSULTANT
---------------



TITLE	HIGH STREET STREETSCAPE CLINTON, MA  GRADING PLAN
BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	29 OF 60


UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION







O:\61005\6182 - CLINTON - HIGH ST STREETS\SCAPEDRAWING FILES\PLANSET\6182 GRADING PLAN.DWG (BETA STB B\W\STB)



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:  
NJM  
DESIGNED BY:  
CJT  
CHECKED BY:  
TJL

REGISTERED PROFESSIONAL

PREPARED BY



SUBCONSULTANT

SCALE



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

HIGH STREET STREETScape  
CLINTON, MA  
GRADING PLAN

BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 31 OF 60






BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 32 OF 60



O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 GRADING PLAN.DWG (BETA STB B\N\STB)




NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NUM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL	PREPARED BY



SUBCONSULTANT





TITLE	HIGH STREET STREETSCAPE CLINTON, MA  GRADING PLAN
-------	------------------------------------------------------------

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	33 OF 60



O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 GRADING PLAN.DWG (BETA STB BW.STB)



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:  
INITIALS  
DESIGNED BY:  
INITIALS  
CHECKED BY:  
INITIALS

REGISTERED PROFESSIONAL  
BETA  
www.BETA-Inc.com



PREPARED BY  
SUBCONSULTANT

SCALE  
20 0 20 40  
SCALE IN FEET: 1"=20'

TITLE  
HIGH STREET STREETSCAPE  
CLINTON, MA  
GRADING PLAN

BETA JOB NO. 6182  
ISSUE DATE 7/16/2020  
SHEET NO. 34 OF 60





SUBCONSULTANT
---------------



TITLE
-------

BETA JOB NO.	6182
--------------	------

ISSUE DATE \_\_\_\_\_ ##/##/####


SHEET NO. 35 OF 60

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS







[illegible]



REGISTERED PROFESSIONAL



SCALE	
-------	--

TITLE
-------





O:\61005\6182 - CLINTON - HIGH ST STREETScape\DRAWING FILES\PLANSET\6182 SIGN AND PAVEMENT MARKING PLAN.DWG (BETA STB.BW/STB)


NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:  
INITIALS  
DESIGNED BY:  
INITIALS  
CHECKED BY:  
INITIALS

REGISTERED PROFESSIONAL  
PREPARED BY



SUBCONSULTANT



TITLE


**HIGH STREET STREETScape  
CLINTON, MA**

**SIGN & PAVEMENT MARKING PLAN**

BETA JOB NO. 6182  
ISSUE DATE #####  
SHEET NO. 38 OF 60



O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 SIGN AND PAVEMENT MARKING PLAN.DWG (BETA STB BW.STB)



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	INITIALS
DESIGNED BY:	INITIALS
CHECKED BY:	INITIALS

REGISTERED PROFESSIONAL


PREPARED BY



www.BETA-Inc.com

SUBCONSULTANT

SCALE



SCALE IN FEET: 1"=20'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE


**HIGH STREET STREETSCAPE  
CLINTON, MA**

**SIGN & PAVEMENT MARKING PLAN**

BETA JOB NO.	6182
ISSUE DATE	###/###/####
SHEET NO.	39 OF 60



O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 SIGN AND PAVEMENT MARKING PLAN.DWG (BETA STB.BW.STB)



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	INITIALS
DESIGNED BY:	INITIALS
CHECKED BY:	INITIALS

REGISTERED PROFESSIONAL


PREPARED BY



www.BETA-Inc.com

SUBCONSULTANT

SCALE



SCALE IN FEET: 1"=20'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE








**HIGH STREET STREETSCAPE  
CLINTON, MA**









**SIGN & PAVEMENT MARKING PLAN**


BETA JOB NO.	6182
ISSUE DATE	###/###/####
SHEET NO.	40 OF 60



7/16/2020 10:53 AM O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 SIGN SUMMARY.DWG (BETA STB.BW.STB)

IDENTIFI- CATION NUMBER	SIZE OF SIGN		TEXT	DIMENSIONS (in)			NUMBER OF SIGNS REQUIRED	COLOR			POST SIZE AND NUMBER REQUIRED	UNIT AREA IN SQUARE FEET	AREA IN SQUARE FEET
	WIDTH	HEIGHT		LETTER HEIGHT	VERTICAL SPACING	ARROW		BACK- GROUND	LEGEND	BORDER			
R1-1	30 in	30 in		SEE 2009 MUTCD STANDARDS			4	RED	WHITE	WHITE	P-5 4	6.25	25.00
R5-2	30 in	30 in					1	WHITE	BLACK	BLACK	P-5 1	6.25	50.00
R7-8	12 in	18 in					5	WHITE	GREEN	GREEN	P-5 5	1.50	7.50
R7-108	12 in	18 in					39	WHITE	GREEN	GREEN	P-5 (5) MOUNT ON LIGHT POST (32)	1.50	58.50
W11-2	30 in	30 in					1	WHITE	BLACK	BLACK	P-5 1	6.25	50.00
W16-7pL	24 in	12 in					1	WHITE	BLACK	BLACK	P-5 1	2.00	50.00
W16-9P	24 in	12 in					12	FYG	BLACK	BLACK	MOUNT W/ W11-2	2.00	24.00

IDENTIFI- CATION NUMBER	SIZE OF SIGN		TEXT	DIMENSIONS (in)			NUMBER OF SIGNS REQUIRED	COLOR			POST SIZE AND NUMBER REQUIRED	UNIT AREA IN SQUARE FEET	AREA IN SQUARE FEET
	WIDTH	HEIGHT		LETTER HEIGHT	VERTICAL SPACING	ARROW		BACK- GROUND	LEGEND	BORDER			
MA-D3-1A	36 in	12 in		6D/ 4D	2.75 3.25		12	GREEN	WHITE	WHITE	P-5 6	EACH	EACH
MA-D3-1B	36 in	12 in		6D/ 4D	3 3		2	GREEN	WHITE	WHITE	MOUNT W/ MA-D3-1A	EACH	EACH
MA-D3-1C	42 in	12 in		6D/ 4D	3 3		2	GREEN	WHITE	WHITE	MOUNT W/ MA-D3-1A	EACH	EACH
MA-D3-1D	36 in	12 in		6D/ 4D	3 3		2	GREEN	WHITE	WHITE	MOUNT W/ MA-D3-1A	EACH	EACH
MA-D3-1E	48 in	12 in		6D/ 4D	2.75 3.25		2	GREEN	WHITE	WHITE	P-5 1	EACH	EACH
MA-D3-1F	42 in	12 in		6D/ 4D	3 3		2	GREEN	WHITE	WHITE	MOUNT W/ R1-1	EACH	EACH
MA-D3-1G	54 in	12 in		6D/ 4D	3 3		2	GREEN	WHITE	WHITE	MOUNT W/ MA-D3-1A	EACH	EACH
MA-D3-1H	42 in	12 in		6D/ 4D	3 3		2	GREEN	WHITE	WHITE	MOUNT W/ MA-D3-1A	EACH	EACH

					DRAWN BY:	REGISTERED PROFESSIONAL	PREPARED BY	SUBCONSULTANT	SCALE	TITLE	BETA JOB NO. 6182
					INITIALS	<div>For Review Only</div>	<div> www.BETA-Inc.com</div>		NONE	HIGH STREET STREETSCAPE CLINTON, MA  TRAFFIC SIGN SUMMARY	ISSUE DATE 7/16/2020
				DESIGNED BY:	INITIALS						SHEET NO. 41 OF 60
				CHECKED BY:	INITIALS						
NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS							



7/16/2020 10:53 AM O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 TRAFFIC MANAGEMENT PLAN.DWG (BETA STB BW STB)

NOTES:

1. ALL TEMPORARY TRAFFIC CONTROL WORK SHALL CONFORM TO THE 2009 EDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD) AND ALL REVISIONS.
2. ALL SIGN LEGENDS, BORDERS AND MOUNTING SHALL BE IN ACCORDANCE WITH THE MUTCD, EXCEPT THAT BACKGROUND COLOR SHALL BE FLUORESCENT ORANGE, IN ACCORDANCE WITH MASSDOT SPECIFICATIONS.
3. TEMPORARY CONSTRUCTION SIGNING AND ALL OTHER TRAFFIC CONTROL DEVICES SHALL BE IN PLACE PRIOR TO THE START OF ANY WORK.
4. TEMPORARY CONSTRUCTION SIGNING, BARRICADES AND ALL OTHER NECESSARY WORK ZONE TRAFFIC CONTROL DEVICES SHALL BE REMOVED FROM THE HIGHWAY OR COVERED WHEN THEY ARE NOT REQUIRED FOR CONTROL OF TRAFFIC.
5. SIGNS AND SIGN SUPPORTS LOCATED ON OR NEAR THE TRAVELED WAY, AND REFLECTORIZED PLASTIC DRUMS WITH LIGHTING DEVICES MOUNTED ON THEM, MUST PASS THE CRITERIA SET FORTH IN THE "MANUAL FOR ACCESSING SAFETY HARDWARE" (MASH).
6. CONTRACTORS SHALL NOTIFY EACH ABUTTER AT LEAST 24 HOURS IN ADVANCE OF THE START OF ANY WORK THAT WILL REQUIRE THE TEMPORARY CLOSURE OF ACCESS, SUCH AS CONDUIT INSTALLATION, EXISTING PAVEMENT EXCAVATION, TEMPORARY DRIVEWAY PAVEMENT PLACEMENT AND SIMILAR OPERATIONS.
7. THE FIRST TEN PLASTIC DRUMS OF A TAPER SHALL BE MOUNTED WITH SEQUENTIAL FLASHING LIGHTS.
8. THE ADVISORY SPEED LIMIT, IF REQUIRED, SHALL BE DETERMINED BY THE ENGINEER.
9. DISTANCES ARE A GUIDE AND MAY BE ADJUSTED IN THE FIELD BY THE ENGINEER.
10. MAXIMUM SPACING OF TRAFFIC DEVICES IN A TAPER (DRUMS OR CONES) IS EQUAL IN FEET TO THE SPEED LIMIT IN MPH.
11. MINIMUM LANE WIDTH IS TO BE 11 FEET UNLESS OTHERWISE SHOWN. MINIMUM LANE WIDTH TO BE MEASURED FROM THE EDGE OF DRUMS OR MEDIAN BARRIER.
12. ALL SIGNS SHALL BE MOUNTED ON THEIR OWN STANDARD SIGN SUPPORTS.
13. TEMPORARY CONSTRUCTION SIGNING AND ALL OTHER NECESSARY WORK ZONE TRAFFIC CONTROL NOT COVERED IN THE PLAN SHALL REFER TO MASSDOT "STANDARD DETAILS AND DRAWINGS FOR THE DEVELOPMENT OF TRAFFIC MANAGEMENT PLANS".

LEGEND:

- REFLECTORIZED PLASTIC DRUM
- ▨

TYPE III BARRICADE
- ⬢

FLASHING ARROW PANNEL
- ⬢

FLASHING ARROW PANNEL
- ▨

WORK ZONE
- ➡

DIRECTION OF TRAFFIC
- ⬢

IMPACT ATTENUATOR
- ▭

MEDIAN BARRIER
- ▭

MEDIAN BARRIER WITH WARNING LIGHTS
- ⬢

WORK VEHICLE
- ▨

TRUCK MOUNTED ATTENUATOR
- ⬢


TRAFFIC OR PEDESTRIAN SIGNAL
- SIGN
- P

POLICE DETAIL
- F


FLAGGER

TAPER LENGTH

SPEED LIMIT	FORMULA
40 MPH or Less	$L=WS^{\frac{2}{60}}$
45 MPH or Greater	$L=W \times S$
L = TAPER LENGTH IN FEET	
W = WIDTH OF OFFSET IN FEET	
S = POSTED SPEED IN MPH	




LONGITUDINAL DROP-OFF DETAIL  
NOT TO SCALE



LATERAL DROP-OFF DETAIL  
NOT TO SCALE

GENERAL CONSTRUCTION STAGES

1. UTILITY WORK
- a. CONSTRUCT ALL PROPOSED UTILITIES AND ADJUST, ABANDON, REMOVE, OR REMOVE AND RESET, ALL EXISTING UTILITIES, AS SHOWN ON THE PLANS.
- b. CONSTRUCT UNDERGROUNDING OF SERVICES CONDUITS AND DUCT BOXES.
2. WIDENING
- SET CURBING AND PERFORM BOX WIDENING.
3. FULL DEPTH CONSTRUCTION/BOX WIDENING
- a. EXCAVATE ROADWAY FOR WIDENING; PLACE THE GRAVEL SUBBASE, WHILE MAINTAINING TRAFFIC IN EACH DIRECTION ON THE EXISTING ROADWAY.
- b. PLACE CRUSHED STONE AND HOT MIX ASPHALT BASE COURSE OR H.E.S. CONCRETE ON ENTIRE WIDENING ROADWAY.
4. TRAFFIC CONTROL
- INSTALL ALL TRAFFIC SIGNAL EQUIPMENT.
5. SIDEWALKS
- CONSTRUCT SIDEWALKS
6. TOP COURSE AND BINDER COURSE
- PLACE BINDER COURSE (WHERE REQUIRED) FOLLOWED BY TOP COURSE FOR THE ENTIRE LENGTH OF THE PROJECT.
7. PAVEMENT MARKINGS
- INSTALL PAVEMENT MARKINGS.




INTERSECTION PROJECT  
LIMIT SIGNING  
NOT TO SCALE

					DRAWN BY:	REGISTERED PROFESSIONAL	PREPARED BY	SUBCONSULTANT	SCALE	TITLE	BETA JOB NO. 6182
					INITIALS						
					DESIGNED BY:						ISSUE DATE 7/16/2020
					INITIALS						
					CHECKED BY:						
					INITIALS						SHEET NO. 42 OF 60
NUMBER	DATE	MADE BY	CHECKED BY		REVISIONS				UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION		




7/16/2020 10:53 AM O:\61005\6102 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6102 TRAFFIC MANAGEMENT PLAN.DWG (BETA STB BW STB)



**NOTES:**

1. ADDITIONAL ADVANCE WARNING MAY BE NECESSARY.
2. CONTROLS ONLY FOR PEDESTRIAN TRAFFIC ARE SHOWN. VEHICULAR TRAFFIC SHOULD BE HANDLED AS SHOWN ELSEWHERE.
3. STREET LIGHTING SHOULD BE CONSIDERED WHEN LOCATING CONTROL DEVICES.
4. IF THE WORK ZONE DOES NOT PERMIT PEDESTRIANS TO TRAVEL ADJACENT TO IT, TEMPORARY CROSSWALKS WITH APPROPRIATE SIGNS SHOULD BE INSTALLED TO CROSS PEDESTRIANS TO THE OPPOSITE SIDE OF THE STREET AS SHOWN IN PEDESTRIAN BYPASS, AND AS DIRECTED BY THE ENGINEER. TEMPORARY CURB RAMPS WILL BE REQUIRED AT ALL TEMPORARY CROSSWALK LOCATIONS.
5. BYPASS IS TO BE USED IN CONJUNCTION WITH THE PROPOSED LANE CLOSURE DETAILS AND DURING CONSTRUCTION STAGING, AS DIRECTED BY THE ENGINEER.
6. THE TEMPORARY SIDEWALK SHOULD BE A MINIMUM OF 4 FEET WIDE. IF THIS WALKWAY EXCEEDS 200 FEET THEN A 5 FOOT X 5 FOOT PASSING ZONE. (FOR SHORT TERM SETUPS < 10 HOURS, THIS CONDITION MAY BE WAIVED. A NOTE WOULD NEED TO BE INCLUDED IN THE TTCP THAT STATES HOW THE CONTRACTOR SHOULD ADDRESS THIS ISSUE.)

**PEDESTRIAN BYPASS DETAILS**  
NOT TO SCALE




**NOTES:**


- DETAIL I IS CONSIDERED AN EXAMPLE OF A SHORT TERM CLOSURE AND PEDESTRIAN ASSISTANCE (PERSONEL) TO NAVIGATE AROUND THE CLOSURE/WORK AREA COULD BE CONSIDERED AS AN OPTION IN PLACE OF PROVIDING ADA/AAB DEVICES. DETAIL II IS CONSIDERED AN EXAMPLE OF A LONG TERM CLOSURE THAT WOULD REQUIRE ADDITIONAL ADA/AAB COMPLIANT DEVICES. IF A SIDEWALK CLOSURE OR RESTRICTION LASTS FOR MORE THAN ONE (1) WORK SHIFT THEN ADA/AAB COMPLIANCE SHALL BE FOLLOWED.
- WHEN EXISTING PEDESTRIAN FACILITIES ARE DISRUPTED, CLOSED, OR RELOCATED IN A TTC ZONE, TEMPORARY FACILITIES SHALL BE PROVIDED AND THEY SHALL BE DETECTABLE AND INCLUDE ACCESSIBILITY FEATURES CONSISTENT WITH THE FEATURES PRESENT IN THE EXISTING PEDESTRIAN FACILITY.
- A PEDESTRIAN CHANNELIZING DEVICE THAT IS DETECTABLE BY A PERSON WITH A VISUAL DISABILITY TRAVELING WITH THE AID OF A LONG CANE SHALL BE PLACED ACROSS THE FULL WIDTH OF THE CLOSED SIDEWALK.
- WHEN USED, TEMPORARY RAMPS SHALL COMPLY WITH AMERICANS WITH DISABILITIES ACT (SEE FIGURES).
- THE ALTERNATE PATHWAY SHOULD HAVE A SMOOTH CONTINUOUS HARD SURFACE FOR THE ENTIRE LENGTH OF THE TEMPORARY PEDESTRIAN FACILITY.
- THE TEMPORARY SIDEWALK SHOULD BE A MINIMUM OF 4 FEET WIDE. IF THE SIDEWALK EXCEEDS 200 FEET THEN A 5 FOOT BE 5 FOOT PASSING ZONE SHALL BE PROVIDED.
- THE PROTECTIVE REQUIREMENTS OF A TTC WORK ZONE MAY HAVE AN IMPACT IN DETERMINING THE NEED FOR TEMPORARY TRAFFIC BARRIERS AND THEIR USE IN PROVIDING PEDESTRIAN DELINEATION SHOULD BE BASED ON ENGINEERING JUDGMENT .
- CONTROLS ONLY FOR PEDESTRIAN TRAFFIC ARE SHOWN; VEHICULAR TRAFFIC SHOULD BE HANDLED AS SHOWN ELSEWHERE. THESE DETAILS ARE USED IN CONJUNCTION WITH THE PROPOSED LANE CLOSURE DETAILS AND DURING CONSTRUCTION STAGING, AS DETERMINED BY THE ENGINEER.
- AUDIBLE INFORMATION DEVICES SHOULD BE CONSIDERED WHERE MIDBLOCK CLOSINGS AND CHANGED CROSSWALK AREAS CAUSE INADEQUATE COMMUNICATION TO BE PROVIDED TO PEDESTRIANS WHO HAVE VISUAL DISABILITIES.
- EXISTING AUDIBLE DEVICES NO LONGER APPLICABLE DUE TO CONSTRUCTION SHALL BE DISABLED.

**AUDIBLE DEVICES:**

- FOR LONG TERM SIDEWALK CLOSURES (AT A MINIMUM OVERNIGHT) A FORM OF SPEECH MESSAGING FOR PEDESTRIANS WITH VISUAL DISABILITIES SHALL BE PROVIDED. AUDIBLE INFORMATION DEVICES SUCH AS DETECTABLE BARRIERS OR BARRICADES AND OTHER PASSIVE PEDESTRIAN ACTIVATION (MOTION ACTIVATED) DEVICES SHOULD BE CONSIDERED FOR THESE CASES. THESE AUDIBLE DEVICES CAN BE MOUNTABLE OR STAND ALONE.




**TEMPORARY CURB RAMP-PERPENDICULAR TO CURB**  
NOT TO SCALE



**TEMPORARY CURB RAMP-PARALLEL TO CURB**  
NOT TO SCALE



**NOTES:**

1. CURB RAMPS SHALL BE 60 IN. MINIMUM WIDTH WITH A FIRM, STABLE AND NON-SLIP SURFACE.
2. PROTECTIVE EDGING WITH A 2 IN. MINIMUM HEIGHT SHALL BE INSTALLED WHEN THE CURB RAMP OR LANDING PLATFORM HAS A VERTICAL DROP OF 6 IN. OR GREATER OR HAS A SIDE APRON SLOP STEEPER THAN 1:3 (33%). PROTECTIVE EDGING SHOULD BE CONSIDERED WHEN THE CURB RAMPS OR LANDING PLATFORMS HAVE A VERTICAL DROP OF 3 IN. OR MORE.
3. DETECTABLE EDGING WITH 6 IN. MINIMUM HEIGHT AND CONTRASTING COLOR SHALL BE INSTALLED ON ALL CURB RAMP LANDINGS WHERE THE WALKWAY CHANGES DIRECTION (TURNS).
4. THE CURB RAMP WALKWAY AND LANDING AREA SURFACE SHALL BE OF A SOLID CONTINUOUS CONTRASTING COLOR ABUTTING UP TO THE EXISTING SIDEWALK.
5. CURB RAMPS AND LANDINGS SHOULD HAVE A 1:50 (2%) MAX CROSS-SLOPE.
6. CLEAR SPACE OF 48x48 IN. MINIMUM SHALL BE PROVIDED ABOVE AND BELOW THE CURB RAMP.
7. WATER FLOW IN THE GUTTER SYSTEM SHALL HAVE MINIMAL RESTRICTION.
8. LATERAL JOINTS OR GAPS BETWEEN SURFACES SHALL BE LESS THAN 0.5 IN. WIDTH.
9. CHANGES BETWEEN SURFACE HEIGHTS SHOULD NOT EXCEED 0.5 IN. LATERAL EDGES SHOULD BE VERTICAL UP TO 0.25 IN. HIGH, AND BEVELED AT 1:2 BETWEEN 0.25 IN. AND 0.5 IN. HEIGHT.
10. IF A TEMPORARY PEDESTRIAN RAMP LEADS TO A CROSSWALK, THEN A DETECTABLE WARNING PAD MUST BE ADHERED TO THE BASE OF THE RAMP. IF IT LEADS TO A PROTECTED PEDESTRIAN BYPASS THAT DOES NOT CONFLICT WITH VEHICULAR TRAFFIC, THEN A PAD SHALL NOT BE INSTALLED ON THE RAMP.



**TEMPORARY CURB RAMP**  
NOT TO SCALE

- \* LANDING AREA USED TO OVERLAP NON-ADA COMPLIANT SURFACES.
- \*\* DETECTABLE EDGE REMOVED IF A CONTINUOUS SIDEWALK.
- \*\*\* 60 IN. IF AN OBSTRUCTION IS AT BACK OF SIDEWALK



**PEDESTRIAN CHANNELIZING DEVICE**  
NOT TO SCALE

**NOTES:**

- \* THERE SHALL BE A 2 INCH GAP BETWEEN THE HAND-TRAILING EDGE AND ITS SUPPORT.
- \*\* A MAXIMUM 2 INCH GAP BETWEEN THE BOTTOM OF THE BOTTOM RAIL AND THE SURFACE MAY BE USED TO PROVIDE DRAINAGE.
- \*\*\* THE HAND-TRAILING EDGE AND DETECTION PLATE SHALL BE CONTINUOUS THROUGHOUT THE LENGTH OF THE PATH SUCH THAT A PEDESTRIAN USER WITH A LONG CANE CAN FOLLOW IT.

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS	

DRAWN BY:	
INITIALS	
DESIGNED BY:	
INITIALS	
CHECKED BY:	
INITIALS	

REGISTERED PROFESSIONAL	PREPARED BY
For Review Only	



SUBCONSULTANT

SCALE
NONE


UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE
HIGH STREET STREETSCAPE CLINTON, MA TEMPORARY TRAFFIC CONTROL PLAN


BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	43 OF 60





7/16/2020 10:53 AM O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 TRAFFIC MANAGEMENT PLAN.DWG (BETA STB BW.STB)




TWO-LANE ROAD - SHOULDER CLOSED  
NOT TO SCALE




TWO-LANE ROAD - ONE LANE ALTERNATING TRAFFIC  
WITH POLICE DETAIL  
NOT TO SCALE



MA-R2-10a  
NOTE:  
"WORK ZONE"  
BLACK ON ORANGE;  
"SPEEDING FINES DOUBLED"  
BLACK ON WHITE



MA-R2-10e  
NOTE:  
"END ROAD WORK"  
BLACK ON ORANGE;  
"DOUBLE FINES END"  
BLACK ON WHITE



W13-1  
24" x 30"



W20-1A  
36" x 36"




W20-1B  
36" x 36"



W21-5aR  
30" x 30"

CONSTRUCTION SIGNS  
NOT TO SCALE



INTERSECTION WITH LANE CLOSURE  
NOT TO SCALE

SAFETY SIGNING FOR CONSTRUCTION OPERATIONS

LEGEND	TYPE	SIZE	COLOR			UNIT AREA	NO. SIGNS	TOTAL AREA	POSTS
			BACKGROUND	LEGEND	BORDER				
WORK ZONE SPEEDING FINES...	MA-R2-10a	48" x 36"	ORANGE**/WHITE	BLACK	BLACK	12 SF	4	48 SF	P-5: 4
END ROAD WORK	MA-R2-10e	36" x 48"	ORANGE**/WHITE	BLACK	BLACK	12 SF	9	108 SF	P-5: 9
SIDEWALK CLOSED CROSS HERE	R9-11a	48" x 24"	WHITE	BLACK	BLACK	8 SF	2	16 SF	P-5: 2
ROAD NARROWS	W5-1	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	2	18 SF	P-5: 2
BUMP	W8-1	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	4	36 SF	P-5: 4
PAVEMENT ENDS	W8-3	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	4	36 SF	P-5: 4
GROOVED PAVEMENT	W8-15	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	4	36 SF	P-5: 4
STEEL PLATE AHEAD	W8-24	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	4	36 SF	P-5: 4
PEDESTRIAN	W11-2	30" x 30"	FYG***	BLACK	BLACK	6.3 SF	4	25 SF	P-5: 4
ADVISORY SPEED	W13-1	24" x 30"	ORANGE**	BLACK	BLACK	5 SF	2	10 SF	P-5: 0
DOWNWARD LEFT DIAGONAL ARROW	W16-7pL	24" x 12"	FYG***	BLACK	BLACK	2 SF	4	8 SF	P-5: 0
ROAD WORK 1500 FT	W20-1A	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	4	36 SF	P-5: 4
ROAD WORK AHEAD	W20-1B	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	9	81 SF	P-5: 9
ONE LANE ROAD AHEAD	W20-4	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	4	36 SF	P-5: 4
ONE LANE ROAD 1000 FT	W20-4C	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	4	36 SF	P-5: 4
FLAGGER	W20-7	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	4	36 SF	P-5: 4
POLICE OFFICER AHEAD	MA-W20-7b	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	4	36 SF	P-5: 4
RIGHT SHOULDER CLOSED	W21-5aR	36" x 36"	ORANGE**	BLACK	BLACK	9 SF	2	18 SF	P-5: 2
TOTAL AREA OF SIGNS:								820 SF	P-5: 68

\* NO. OF SIGNS ARE ESTIMATED FOR BIDDING PURPOSES ONLY

\*\* ALL CONSTRUCTION SIGNAGE SHALL HAVE FLUORESCENT ORANGE BACKGROUND

\*\*\* FLUORESCENT YELLOW GREEN

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	INITIALS
DESIGNED BY:	INITIALS
CHECKED BY:	INITIALS

REGISTERED PROFESSIONAL  
For Review Only



SUBCONSULTANT

SCALE

NONE

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE


HIGH STREET STREETSCAPE  
CLINTON, MA  
TEMPORARY TRAFFIC  
CONTROL PLAN

BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 44 OF 60






PLANT SCHEDULE LANDSCAPE PLAN 1

TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER
GTH	6	Gleditsia triacanthos inermis 'Halka'	Halka Thornless Honey Locust	2.5"-3" Cal.	B&B

- NOTES:
- ALL DECORATIVE LIGHT POLES AND LUMINAIRES SHALL BE TYPE A - (SINGLE POST TOP) UNLESS NOTED AS TYPE B. REFER TO LA DETAIL AREAS 1 AND 3. FOR LOCATIONS SEE LAYOUT PLANS AND ELECTRICAL PLANS.
  - COORDINATE ALL CONDUIT, HANDHOLES AND IRRIGATION SYSTEM COMPONENTS WITH HARDSCAPE AND PLANTINGS.



OVERALL PROJECT TOTAL PLANT SCHEDULE

TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	
GTH	14	Gleditsia triacanthos inermis 'Halka'	Halka Thornless Honey Locust	2.5"-3" Cal.	B&B	
LSS	6	Liquidambar styraciflua 'Slender Silhouette'	Columnar Sweet Gum	2.5"-3" Cal.	B&B	
PSC	9	Prunus sargentii 'Columnaris'	Columnar Sargent Cherry	2.5"-3" Cal.	B&B	
QGP	6	Quercus palustris 'Pringreen' TM	Greenpillar Pin Oak	2.5"-3" Cal.	B&B	
TD	10	Taxodium distichum	Bald Cypress	16'-18' Ht.	B&B	
ZGV	9	Zelkova serrata 'Green Vase'	Green Vase Sawleaf Zelkova	2.5"-3" Cal.	B&B	
SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	
CBM	6	Caryopteris x clandonensis 'Blue Mist'	Blue Mist Bluebeard	3 gal.	Cont.	
TMH	6	Taxus x media 'Hicksii'	Hicks Yew	4'-5' Ht.	B&B	
SHRUB AREAS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	SPACING
CKF	58	Calamagrostis x acutiflora 'Karl Foerster'	Feather Reed Grass	2 gal.	Cont.	30" o.c.
HSO	265	Hemerocallis x 'Stella de Oro'	Stella de Oro Daylily	1 gal.	Cont.	18" o.c.
JBH	22	Juniperus horizontalis 'Bar Harbor'	Bar Harbor Creeping Juniper	15"-18"	Cont.	30" o.c.
LBB	277	Liriope muscari 'Big Blue'	Big Blue Lilyturf	1 gal.	Cont.	15" o.c.
NWL	135	Nepeta x faassenii 'Walkers Low'	Walkers Low Catmint	1 gal.	Cont.	30" o.c.
PAH	193	Pennisetum alopecuroides 'Hameln'	Hameln Fountain Grass	3 gal.	Cont.	24" o.c.

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS	

DRAWN BY:	INITIALS
DESIGNED BY:	INITIALS
CHECKED BY:	INITIALS

REGISTERED PROFESSIONAL

PREPARED BY



SUBCONSULTANT

SCALE



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

HIGH STREET STREETSCAPE  
CLINTON, MA  
  
HIGH ST. LANDSCAPE PLAN 1


BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 45 OF 60



7/16/2020 10:54 AM O:\6105\6182 - CLINTON - HIGH ST STREETSCLAPEDRAWING FILES\PLANSET\6182 - LANDSCAPE PLAN.DWG (BETA STB BW.STB)



PLANT SCHEDULE LANDSCAPE PLAN 2

TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER
GTH	2	Gleditsia triacanthos inermis 'Halka'	Halka Thornless Honey Locust	2.5"-3" Cal.	B&B
QGP	4	Quercus palustris 'Pringreen' TM	Greenpillar Pin Oak	2.5"-3" Cal.	B&B
ZGV	7	Zelkova serrata 'Green Vase'	Green Vase Sawleaf Zelkova	2.5"-3" Cal.	B&B

- NOTES:
- ALL DECORATIVE LIGHT POLES AND LUMINAIRES SHALL BE TYPE A - (SINGLE POST TOP) UNLESS NOTED AS TYPE B. REFER TO LA DETAIL AREAS 1 AND 3. FOR LOCATIONS SEE LAYOUT PLANS AND ELECTRICAL PLANS.
  - COORDINATE ALL CONDUIT, HANDHOLES AND IRRIGATION SYSTEM COMPONENTS WITH HARDSCAPE AND PLANTINGS.

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	INITIALS
DESIGNED BY:	INITIALS
CHECKED BY:	INITIALS

REGISTERED PROFESSIONAL

PREPARED BY

SUBCONSULTANT



SCALE



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

HIGH STREET STREETScape  
CLINTON, MA

HIGH ST. LANDSCAPE PLAN 2


BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 46 OF 60



7/16/2020 10:54 AM O:\61005\6182 - CLINTON - HIGH ST STREETScape\DRAWING FILES\PLANSET\6182 LANDSCAPE PLAN DWG (BETA STB BW.STB)



PLANT SCHEDULE LANDSCAPE PLAN 3

TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER
LSS	6	Liquidambar styraciflua 'Slender Silhouette'	Columnar Sweet Gum	2.5'-3' Cal.	B&B
PSC	1	Prunus sargentii 'Columnaris'	Columnar Sargent Cherry	2.5'-3' Cal.	B&B
SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER
CBM	6	Caryopteris x clandonensis 'Blue Mist'	Blue Mist Bluebeard	3 gal.	Cont.
TMH	6	Taxus x media 'Hicksii'	Hicks Yew	4'-5' Ht.	B&B

- NOTES:
- ALL DECORATIVE LIGHT POLES AND LUMINAIRES SHALL BE TYPE A - (SINGLE POST TOP) UNLESS NOTED AS TYPE B. REFER TO LA DETAIL AREAS 1 AND 3. FOR LOCATIONS SEE LAYOUT PLANS AND ELECTRICAL PLANS.
  - COORDINATE ALL CONDUIT, HANDHOLES AND IRRIGATION SYSTEM COMPONENTS WITH HARDSCAPE AND PLANTINGS.

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	INITIALS
DESIGNED BY:	INITIALS
CHECKED BY:	INITIALS

REGISTERED PROFESSIONAL

PREPARED BY

**BETA**

www.BETA-Inc.com

SUBCONSULTANT

SCALE

20 0 20 40

SCALE IN FEET: 1"=20'

UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION


TITLE

**HIGH STREET STREETSCAPE  
CLINTON, MA**

**HIGH ST. LANDSCAPE PLAN 3**

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	47 OF 60






PLANT SCHEDULE LANDSCAPE PLAN 4

TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER
PSC	2	Prunus sargentii 'Columnaris'	Columnar Sargent Cherry	2.5"-3" Cal.	B&B
TD	1	Taxodium distichum	Bald Cypress	16'-18' Ht.	B&B

- NOTES:
1.

ALL DECORATIVE LIGHT POLES AND LUMINAIRES SHALL BE TYPE A - (SINGLE POST TOP) UNLESS NOTED AS TYPE B. REFER TO LA DETAIL AREAS 1 AND 3. FOR LOCATIONS SEE LAYOUT PLANS AND ELECTRICAL PLANS.
2.

COORDINATE ALL CONDUIT, HANDHOLES AND IRRIGATION SYSTEM COMPONENTS WITH HARDSCAPE AND PLANTINGS.



7/16/2020 10:54 AM O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 LANDSCAPE PLAN.DWG (BETA STB BW.STB)

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS


DRAWN BY:	INITIALS
DESIGNED BY:	INITIALS
CHECKED BY:	INITIALS

REGISTERED PROFESSIONAL

PREPARED BY

  
www.BETA-Inc.com

SUBCONSULTANT



TITLE


HIGH STREET STREETSCAPE  
CLINTON, MA

HIGH ST. LANDSCAPE PLAN 4

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	48 OF 60




7/16/2020 10:54 AM O:\6105\6182 - CLINTON - HIGH ST STREETSCLAPEDRAWING FILES\PLANSET\6182 LANDSCAPE PLAN.DWG (BETA STB BW.STB)



PLANT SCHEDULE LANDSCAPE PLAN 5

TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER
GTH	3	Gleditsia triacanthos inermis 'Halka'	Halka Thornless Honey Locust	2.5"-3" Cal.	B&B
PSC	4	Prunus sargentii 'Columnaris'	Columnar Sargent Cherry	2.5"-3" Cal.	B&B
QGP	2	Quercus palustris 'Pringreen' TM	Greenpillar Pin Oak	2.5"-3" Cal.	B&B

- NOTES:
- ALL DECORATIVE LIGHT POLES AND LUMINAIRES SHALL BE TYPE A - (SINGLE POST TOP) UNLESS NOTED AS TYPE B. REFER TO LA DETAIL AREAS 1 AND 3. FOR LOCATIONS SEE LAYOUT PLANS AND ELECTRICAL PLANS.
  - COORDINATE ALL CONDUIT, HANDHOLES AND IRRIGATION SYSTEM COMPONENTS WITH HARDSCAPE AND PLANTINGS.



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:  
INITIALS  
DESIGNED BY:  
INITIALS  
CHECKED BY:  
INITIALS

REGISTERED PROFESSIONAL PREPARED BY



SUBCONSULTANT

SCALE



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

HIGH STREET STREETScape  
CLINTON, MA

CHURCH ST. LANDSCAPE PLAN 1


BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 49 OF 60




7/16/2020 10:54 AM O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 - LANDSCAPE PLAN.DWG (BETA STB BW.STB)



PLANT SCHEDULE LA DETAIL AREA 1

<u>TREES</u>	<u>QTY</u>	<u>BOTANICAL NAME</u>	<u>COMMON NAME</u>	<u>SIZE</u>	<u>CONTAINER</u>	
TD	2	Taxodium distichum	Bald Cypress	16'-18' Ht.	B&B	
<u>SHRUB AREAS</u>	<u>QTY</u>	<u>BOTANICAL NAME</u>	<u>COMMON NAME</u>	<u>SIZE</u>	<u>CONTAINER</u>	<u>SPACING</u>
CKF	19	Calamagrostis x acutiflora 'Karl Foerster'	Feather Reed Grass	2 gal.	Cont.	30" o.c.
HSO	119	Hemerocallis x 'Stella de Oro'	Stella de Oro Daylily	1 gal.	Cont.	18" o.c.
LBB	65	Liriope muscari 'Big Blue'	Big Blue Lilyturf	1 gal.	Cont.	15" o.c.
NWL	58	Nepeta x faassenii 'Walkers Low'	Walkers Low Catmint	1 gal.	Cont.	30" o.c.
PAH	69	Pennisetum alopecuroides 'Hameln'	Hameln Fountain Grass	3 gal.	Cont.	24" o.c.

LA DETAIL AREA 1  
SCALE: 1"=10'-0"



PLANT SCHEDULE LA DETAIL AREA 2

TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	
GTH	1	Gleditsia triacanthos inermis 'Halka'	Halka Thornless Honey Locust	2.5"-3" Cal.	B&B	
TD	2	Taxodium distichum	Bald Cypress	16'-18" HT.	B&B	
SHRUB AREAS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	SPACING
CKF	17	Calamagrostis x acutiflora 'Karl Foerster'	Feather Reed Grass	2 gal.	Cont.	30" o.c.
HSO	32	Hemerocallis x 'Stella de Oro'	Stella de Oro Daylily	1 gal.	Cont.	18" o.c.
LBB	42	Liriope muscari 'Big Blue'	Big Blue Lilyturf	1 gal.	Cont.	15" o.c.
NWL	16	Nepeta x faassenii 'Walkers Low'	Walkers Low Catmint	1 gal.	Cont.	30" o.c.
PAH	11	Pennisetum alopecuroides 'Hameln'	Hameln Fountain Grass	3 gal.	Cont.	24" o.c.

LA DETAIL AREA 2  
SCALE: 1"=10'-0"

- NOTES:
- ALL DECORATIVE LIGHT POLES AND LUMINAIRES SHALL BE TYPE A - (SINGLE POST TOP) UNLESS NOTED AS TYPE B. REFER TO LA DETAIL AREAS 1 AND 3. FOR LOCATIONS SEE LAYOUT PLANS AND ELECTRICAL PLANS.
  - COORDINATE ALL CONDUIT, HANDHOLES AND IRRIGATION SYSTEM COMPONENTS WITH HARDSCAPE AND PLANTINGS.

NUMBER	DATE	MADE BY	CHECKED BY		REVISIONS

DRAWN BY:	INITIALS
DESIGNED BY:	INITIALS
CHECKED BY:	INITIALS

REGISTERED PROFESSIONAL	PREPARED BY
-------------------------	-------------




SUBCONSULTANT
---------------


SCALE
10 0 10 20
SCALE IN FEET: 1"=10'
UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE	HIGH STREET STREETSCAPE CLINTON, MA LANDSCAPE DETAIL AREAS - ENLARGEMENT PLAN 1
BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	50 OF 60







PLANT SCHEDULE LA DETAIL AREA 3						
TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	
GTH	2	Gleditsia triacanthos inermis 'Halka'	Halka Thornless Honey Locust	2.5'-3" Cal.	B&B	
SHRUB AREAS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	SPACING
CKF	22	Calamagrostis x acutiflora 'Karl Foerster'	Feather Reed Grass	2 gal.	Cont.	30" o.c.
JBH	22	Juniperus horizontalis 'Bar Harbor'	Bar Harbor Creeping Juniper	15'-18"	Cont.	30" o.c.
LBB	48	Liriope muscari 'Big Blue'	Big Blue Lilyturf	1 gal.	Cont.	15" o.c.
NWL	16	Nepeta x faassenii 'Walkers Low'	Walkers Low Catmint	1 gal.	Cont.	30" o.c.
PAH	15	Pennisetum alopecuroides 'Hameln'	Hameln Fountain Grass	3 gal.	Cont.	24" o.c.
LA DETAIL AREA 3						
SCALE: 1"=10'-0"						



PLANT SCHEDULE LA DETAIL AREA 5						
TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	
TD	1	Taxodium distichum	Bald Cypress	16'-18' Ht.	B&B	
SHRUB AREAS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	SPACING
HSO	20	Hemerocallis x 'Stella de Oro'	Stella de Oro Daylily	1 gal.	Cont.	18" o.c.
LBB	34	Liriope muscari 'Big Blue'	Big Blue Lilyturf	1 gal.	Cont.	15" o.c.
PAH	14	Pennisetum alopecuroides 'Hameln'	Hameln Fountain Grass	3 gal.	Cont.	24" o.c.
LA DETAIL AREA 5						
SCALE: 1"=10'-0"						



PLANT SCHEDULE LA DETAIL AREA 6						
TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	
TD	2	Taxodium distichum	Bald Cypress	16'-18' Ht.	B&B	
SHRUB AREAS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	SPACING
HSO	49	Hemerocallis x 'Stella de Oro'	Stella de Oro Daylily	1 gal.	Cont.	18" o.c.
LBB	88	Liriope muscari 'Big Blue'	Big Blue Lilyturf	1 gal.	Cont.	15" o.c.
PAH	22	Pennisetum alopecuroides 'Hameln'	Hameln Fountain Grass	3 gal.	Cont.	24" o.c.
LA DETAIL AREA 6						
SCALE: 1"=10'-0"						



PLANT SCHEDULE LA DETAIL AREA 4						
TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	
PSC	2	Prunus sargentii 'Columnaris'	Columnar Sargent Cherry	2.5'-3" Cal.	B&B	
TD	2	Taxodium distichum	Bald Cypress	16'-18' Ht.	B&B	
ZGV	2	Zelkova serrata 'Green Vase'	Green Vase Sawleaf Zelkova	2.5'-3" Cal.	B&B	
SHRUB AREAS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CONTAINER	SPACING
HSO	45	Hemerocallis x 'Stella de Oro'	Stella de Oro Daylily	1 gal.	Cont.	18" o.c.
NWL	45	Nepeta x faassenii 'Walkers Low'	Walkers Low Catmint	1 gal.	Cont.	30" o.c.
PAH	62	Pennisetum alopecuroides 'Hameln'	Hameln Fountain Grass	3 gal.	Cont.	24" o.c.
LA DETAIL AREA 4						
SCALE: 1"=10'-0"						


NOTES:  
1. ALL DECORATIVE LIGHT POLES AND LUMINAIRES SHALL BE TYPE A - (SINGLE POST TOP) UNLESS NOTED AS TYPE B. REFER TO LA DETAIL AREAS 1 AND 3. FOR LOCATIONS SEE LAYOUT PLANS AND ELECTRICAL PLANS.  
2. COORDINATE ALL CONDUIT, HANDHOLES AND IRRIGATION SYSTEM COMPONENTS WITH HARDSCAPE AND PLANTINGS.

7/16/2020 10:55 AM O:\61005\6102 - CLINTON - HIGH ST. STREETSCAPE\DRAWING FILES\PLANSET\6102 LANDSCAPE PLAN.DWG (BETA STB BW.STB)


<table><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td></tr><tr><td>NUMBER</td><td>DATE</td><td>MADE BY</td><td>CHECKED BY</td></tr></table>																									NUMBER	DATE	MADE BY	CHECKED BY	<table><tr><td>DRAWN BY:</td><td>REGISTERED PROFESSIONAL</td></tr><tr><td>INITIALS</td><td> </td></tr><tr><td>DESIGNED BY:</td><td>PREPARED BY</td></tr><tr><td>INITIALS</td><td> </td></tr><tr><td>CHECKED BY:</td><td>SUBCONSULTANT</td></tr><tr><td>INITIALS</td><td> </td></tr></table>	DRAWN BY:	REGISTERED PROFESSIONAL	INITIALS		DESIGNED BY:	PREPARED BY	INITIALS		CHECKED BY:	SUBCONSULTANT	INITIALS		<table><tr><td>SCALE</td><td>TITLE</td></tr><tr><td> UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION</td><td><b>HIGH STREET STREETSCAPE CLINTON, MA LANDSCAPE DETAIL AREAS - ENLARGEMENT PLAN 1</b></td></tr></table>	SCALE	TITLE	 UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION	<b>HIGH STREET STREETSCAPE CLINTON, MA LANDSCAPE DETAIL AREAS - ENLARGEMENT PLAN 1</b>	<table><tr><td>BETA JOB NO. 6182</td></tr><tr><td>ISSUE DATE 7/16/2020</td></tr><tr><td>SHEET NO. 51 OF 60</td></tr></table>	BETA JOB NO. 6182	ISSUE DATE 7/16/2020	SHEET NO. 51 OF 60
NUMBER	DATE	MADE BY	CHECKED BY																																															
DRAWN BY:	REGISTERED PROFESSIONAL																																																	
INITIALS																																																		
DESIGNED BY:	PREPARED BY																																																	
INITIALS																																																		
CHECKED BY:	SUBCONSULTANT																																																	
INITIALS																																																		
SCALE	TITLE																																																	
 UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION	<b>HIGH STREET STREETSCAPE CLINTON, MA LANDSCAPE DETAIL AREAS - ENLARGEMENT PLAN 1</b>																																																	
BETA JOB NO. 6182																																																		
ISSUE DATE 7/16/2020																																																		
SHEET NO. 51 OF 60																																																		




7/16/2020 10:56 AM O:\6105\6102 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6102 LANDSCAPE DETAILS.DWG (BETA STB BIV/STB)




**PLANT BED SECTION - REFER TO LA DETAIL AREA 6**  
SCALE: 1"=1'-0"




**SECTION / ELEVATION OF LIGHT POLE AT CURB**  
SCALE: 1"=1'-0"




**GRANITE COBBLESTONE ACCENT BAND AND PLANT BED - SECTION**  
SCALE: 1"=1'-0"




**GRANITE COBBLESTONE ACCENT BAND AT CORNER**  
SCALE: 1"=1'-0"



**COBBLESTONE ACCENT BAND AT RADIAL CURB**  
SCALE: 1"=1'-0"



**COBBLESTONE ACCENT BAND AT STRAIGHT CURB**  
SCALE: 1"=1'-0"



**COBBLESTONE ACCENT BAND - SECTION AT CURB**  
SCALE: 1"=1'-0"

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	INITIALS
DESIGNED BY:	INITIALS
CHECKED BY:	INITIALS

REGISTERED PROFESSIONAL  
**For Review Only**



SUBCONSULTANT

SCALE  
AS SHOWN

TITLE  
**HIGH STREET STREETSCAPE  
CLINTON, MA  
LANDSCAPE DETAILS**

BETA JOB NO. 6182  
ISSUE DATE 7/16/2020  
SHEET NO. 52 OF 60












DRAINAGE STRUCTURE TABLE						
NAME	STATION	OFFSET	RIMS	INV. ELEV. IN	INV. ELEV. OUT	REMARKS
CBCI-1	0+65.14	27.3 R	340.12'		I=336.72' (CIT-1)	
CBCI-3	110+87.68	23.6 R	340.01'		I=336.61' (CIT-3)	
CIT-1	0+40.34	27.2 R	340.51'	I=336.47' (CBCI-1)	EXIST INVERT	
CIT-3	111+02.34	21.9 R	340.45'	I=336.45' (CBCI-3)	EXIST INVERT	

UTILITY PLANS GENERAL NOTES:

1. ALL EXISTING UTILITY STRUCTURES SHALL BE RETAINED UNLESS OTHERWISE NOTED OR AT THE DIRECTION OF THE ENGINEER.
2. UTILITY POLES TO BE RETAINED UNLESS OTHERWISE NOTED. EXISTING LIGHT FIXTURES MOUNTED ON UTILITY POLES MOUNTED ON UTILITY POLE SHALL BE REMOVED BY OTHERS.
3. TEST PITS FOR POTENTIAL UTILITY CONFLICTS SHALL BE COMPLETED PRIOR TO ANY UTILITY CONSTRUCTION IS PERFORMED (MIN. 30 DAYS PRIOR). ALL RESULTS TO ENGINEER FOR REVIEW.
4. EXISTING DRAINAGE, WATER OR SEWER PIPE WITHIN THE ALIGNMENT OF THE PROPOSED PIPE SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AS PART OF THE WORK TO INSTALL NEW PIPE.
5. ALL EXISTING PRIVATE UTILITY STRUCTURES SHALL BE ADJUSTED AS NECESSARY TO THE PROPOSED FINISH GRADE BY OTHERS UNLESS OTHERWISE NOTED ON THE PLANS.
6. ALL CATCH BASINS AND MANHOLES SHALL HAVE CONCENTRIC CONE TOPS UNLESS OTHERWISE NOTED ON THE PLANS.
7. ALL WATER SERVICE BOXES / WATER SHUT OFFS TO ABUTTERS SHALL BE ADJUSTED UNLESS OTHERWISE NOTED ON THE PLANS. THE CONTRACTOR IS ADVISED THAT WATER SERVICE BOXES (WSO) MAY BE BURIED. BURIED BOXES SHALL ALSO BE ADJUSTED.
8. ANY CHANGES TO THE PROPOSED DRAINAGE, INCLUDING INVERTS AND LOCATIONS, SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW.



O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 UTILITIES PLAN.DWG (BETA STB BW.STB)

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS	

DRAWN BY:	REG
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL

PREPARED BY



SUBCONSULTANT

SCALE



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

HIGH STREET STREETSCAPE  
CLINTON, MA  
UTILITIES PLAN


BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 55 OF 60



O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 UTILITIES PLAN.DWG (BETA STB BWS\STB)



DRAINAGE STRUCTURE TABLE						
NAME	STATION	OFFSET	RIMS	INV. ELEV. IN	INV. ELEV. OUT	REMARKS
CBCI-2	4+32.33	28.0 R	343.25'		EXIST PIPE ELEV	
CBCI-4	5+67.65	27.2 L	341.19'		I=337.02' (DMH-2)	
CBCI-5	3+48.19	27.8 L	342.10'		I=338.66' (DMH-1)	
CBCI-6	4+32.12	28.0 L	341.90'		I=337.91' (DMH-1)	
CBCI-7	7+47.35	26.9 L	336.59'		I=332.42' (DMH-3)	
CBCI-21	204+06.21	17.6 R	343.74'		EXIST PIPE ELEV	
CIT-2	4+78.39	28.1 L	342.57'	I=337.24' (DMH-1)	EXIST PIPE ELEV	
DMH-1	4+32.49	18.2 L	345.60'	I=337.81' (CBCI-5) I=337.81' (CBCI-6)	I=337.71' (CIT-2)	
DMH-2	5+67.34	9.0 L	341.71'	I=336.84' (CBCI-4)	EXIST PIPE ELEV	OVER EXIST PIPE
DMH-3	7+47.43	9.2 L	337.25'	I=332.24' (CBCI-7)	EXIST PIPE ELEV	OVER EXIST PIPE

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NJM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL

PREPARED BY

SUBCONSULTANT



SCALE



UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE

HIGH STREET STREETSCAPE  
CLINTON, MA  
  
UTILITIES PLAN


BETA JOB NO. 6182

ISSUE DATE 7/16/2020

SHEET NO. 56 OF 60



O:\61005\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 UTILITIES PLAN.DWG (BETA STB BWS\STB)



DRAINAGE STRUCTURE TABLE						
NAME	STATION	OFFSET	RIMS	INV. ELEV. IN	INV. ELEV. OUT	REMARKS
DMH-4	9+01.85	26.1 R	333.42'	I=331.12' (CB-10) I=330.41' (DMH-5)	I=329.25' (CIT-4)	FLAT TOP, 4" FRAME
DMH-5	9+22.03	25.7 R	332.93'	I=330.61' (CBCI-9)	I=330.51' (DMH-4)	FLAT TOP, 4" FRAME
DMH-6	12+34.86	17.6 R	328.74'	I=326.44' (CB-12) I=325.86' (CB-13)	EXIST PIPE ELEV	FLAT TOP, 4" FRAME, OVER EXIST PIPE
DMH-7	13+98.68	25.0 R	325.58'	I=322.18' (CB-14) I=321.48' (CB-15)	I=321.39' (DMH-8)	ECCENTRIC
DMH-8	13+98.60	12.1 L	324.52'	I=318.19' (DMH-9) I=321.02' (DMH-7)	I=318.09' (EX DMH-4)	
EX DMH-1	9+15.28	9.4 L	332.63'	I=327.48' (CBCI-8)	EXIST INVERT	
EX DMH-2	11+05.74	20.4 L	328.86'	I=325.43' (CBCI-10)	EXIST INVERT	
EX DMH-3	12+36.07	9.7 L	327.94'	I=322.83' (CBCI-11)	EXIST INVERT	
EX DMH-4	12+84.21	11.8 L	327.14'	I=317.52' (DMH-8)	EXIST INVERT	


DRAINAGE STRUCTURE TABLE						
NAME	STATION	OFFSET	RIMS	INV. ELEV. IN	INV. ELEV. OUT	REMARKS
CB-10	9+02.58	39.6 R	334.45'		I=332.15' (DMH-4)	FLAT TOP, 4" FRAME
CB-12	12+56.49	38.2 R	329.46'		I=327.16' (DMH-6)	FLAT TOP, 4" FRAME
CB-13	12+25.28	37.8 R	331.41'		I=326.08' (DMH-6)	
CB-14	13+98.63	38.1 R	326.13'	I=322.73' ( )	I=322.63' (DMH-7)	CONNECT TO EXIST PVC PIPE
CB-15	14+17.54	24.5 R	325.07'		I=321.67' (DMH-7)	ECCENTRIC
CBCI-8	9+09.22	26.8 L	331.83'		I=327.66' (EX DMH-1)	
CBCI-9	9+20.07	42.5 R	334.29'		I=331.99' (DMH-5)	FLAT TOP, 4" FRAME
CBCI-10	10+99.70	26.6 L	328.72'		I=325.52' (EX DMH-2)	
CBCI-11	12+40	27.3 L	327.21'		I=323.01' (EX DMH-3)	
CIT-4	8+86.40	26.5 R	335.67'	I=329.10' (DMH-4)	EXIST INVERT	

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	REGISTERED PROFESSIONAL	PREPARED BY
NJM		
DESIGNED BY:		
CJT		
CHECKED BY:		
TJL		




SUBCONSULTANT



TITLE
HIGH STREET STREETSCAPE CLINTON, MA
UTILITIES PLAN

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	57 OF 60





DRAINAGE STRUCTURE TABLE						
NAME	STATION	OFFSET	RIMS	INV. ELEV. IN	INV. ELEV. OUT	REMARKS
CB-16	18+10.41	22.9 L	314.48'		EXIST INVERT	ECCENTRIC, 5' DIA
CB-17	14+88.49	24.4 R	322.61'		I=318.90' (DMH-9)	
CBCI-18	14+71.33	25.6 L	321.97'		I=319.67' (DMH-9)	ECCENTRIC, FLAT TOP, 4" FRAME, 5" DIA
DMH-9	14+83.56	13.2 L	322.07'	I=319.58' (CBCI-18) I=318.71' (CB-17)	I=318.61' (DMH-8)	FLAT TOP, 4" FRAME

REM EXIST GUTTER INLET & MH  
CONNECT NEW CB TO EXIST PIPE

CB  
RIM=314.17

DMH  
RIM=314.48  
INV=312.48 (UNK)  
INV=311.48 (TOP HOOD/UNK)  
INV=310.45 (12" CI)  
INV=308.20 (BOS)  
INV=310.58 (TOW)

SMH  
RIM=312.19  
INV=303.47 (10" VC)

HIGH STREET

SMH  
RIM=314.10  
INV=307.98 (10" VC)

SMH  
RIM=315.47  
INV=305.97 (10" VC)

SB/LDP(FND)FLUSH  
N: 2978542.976'  
E: 606467.697'

DMH  
RIM=317.94  
INV=314.32 (12" RCP)  
INV=314.30 (12" PVC)

SMH  
RIM=319.23  
INV=315.07 (12" RCP)  
INV=314.57 (12" RCP)  
INV=314.53 (12" RCP)

CB  
RIM=319.52

CB  
RIM=323.72

BATTISTA COURT

RICHARDSON PLACE


SB/DH(FND)UP 3  
N: 2978256.958'  
E: 606446.423'

SB/TOP(FND)CNTR  
N: 2978245.849'  
E: 606523.989'

O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 UTILITIES PLAN.DWG (BETA STB B/W STB)

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY: NUM	REGISTERED PROFESSIONAL
DESIGNED BY: CJT	PREPARED BY
CHECKED BY: TJL	SUBCONSULTANT




TITLE
HIGH STREET STREETSCAPE CLINTON, MA  UTILITIES PLAN

BETA JOB NO. 6182
ISSUE DATE 7/16/2020
SHEET NO. 58 OF 60



O:\6105\6182 - CLINTON - HIGH ST STREETSCAPE\DRAWING FILES\PLANSET\6182 UTILITIES PLAN.DWG (BETA STB BWS.TB)



DRAINAGE STRUCTURE TABLE						
NAME	STATION	OFFSET	RIMS	INV. ELEV. IN	INV. ELEV. OUT	REMARKS
CB-20	4+88.22	190.3 R	354.35'		EXIST INVERT	
CBCI-19	4+71.20	280.5 R	359.63'		EXIST INVERT	
CBCI-21	204+06.21	17.6 R	343.74'		EXIST INVERT	


NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	NJM
DESIGNED BY:	CJT
CHECKED BY:	TJL

REGISTERED PROFESSIONAL	PREPARED BY



SUBCONSULTANT



TITLE

**HIGH STREET STREETSCAPE  
CLINTON, MA**

**UTILITIES PLAN**

BETA JOB NO.	6182
ISSUE DATE	7/16/2020
SHEET NO.	59 OF 60










NOTES:

1. ALL WORK SHALL CONFORM TO THE LATEST REVISIONS OF THE NATIONAL ELECTRICAL CODE, THE COMMONWEALTH OF MASSACHUSETTS ROADWAY STANDARDS AND SPECIFICATIONS AND THE REQUIREMENTS FOR THE TOWN OF CLINTON.
2. ALL WORK SHALL BE COORDINATED WITH LOCAL PUBLIC UTILITIES. NO WORK SHALL COMMENCE UNTIL THE CONTRACTOR HAS NOTIFIED DIG-SAFE AND ALL EXISTING UTILITIES HAVE BEEN PROPERLY NOTIFIED. CONTRACTOR SHALL CONFIRM AND VERIFY LOCATION OF ALL EXISTING UTILITIES BEFORE INSTALLATION OF RACEWAY, HANDHOLES, LIGHTING FIXTURES AND POLE BASES. ANY DAMAGE TO THE UTILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
3. ALL LIGHTING CONDUITS SHALL BE 2" PVC SCHEDULE 80 NM (NON-METALLIC), EXCEPT WHERE OTHERWISE SHOWN. INSTALL NYLON PULL STRING IN ALL SPARE CONDUITS FOR FUTURE USE. SERVICE CONDUIT FROM UTILITY TRANSFORMER SHALL BE 3" PVC SCHED 80.
4. ALL RACEWAY SHALL BE INSTALLED AT A MIN DEPTH OF 30", UNLESS DIRECTED BY THE ENGINEER. WHEN MULTIPLE CONDUITS ARE INSTALLED IN THE SAME TRENCH THE CONTRACTOR SHALL INSTALL RACEWAY SPACES AS INCIDENTAL TO THE WORK.
5. PROVIDE LUG REDUCERS AND TERMINATING STUDS AS REQUIRED.
6. CONTRACTOR SHALL COORDINATE AND CONFIRM WITH UTILITY FOR COLD/HOT SEQUENCE METERING REQUIREMENTS.
7. CONTRACTOR SHALL PROVIDE ENOUGH SLACK (CABLE) AT THE HANDHOLES AND PULLBOXES TO ALLOW FOR SPLICING AND REPAIRS TO BE MADE.
8. CONTRACTOR SHALL FURNISH AND INSTALL INDUSTRUCTIBLE, NUMBERING, PLASTIC TAGS ON ALL CIRCUITS AT ALL HANDHOLES AS PER CIRCUITS NOTED ON PLANS.
9. PRIOR TO REMOVING ANY EXISTING ELECTRICAL WIRING AND RACEWAY, CONTRACTOR SHALL CONFIRM AND COORDINATE WITH TOWN OF CLINTON THAT EXISTING WIRING & RACEWAY DOES NOT FEED ANY EXISTING ELECTRICAL DEVICES OUTSIDE OF PROJECT SCOPE. ALL EXISTING DEVICES, OUTSIDE OF PROJECT SCOPE, SHALL REMAIN ACTIVE DURING AND AFTER COMPLETION OF PROJECT.
10. CONTRACTOR SHALL CONFIRM AND COORDINATE REMOVAL OF ALL EXISTING LIGHTING FIXTURE POLES AND LUMINAIRES, WITHIN THE PROJECT LIMITS, WITH THE TOWN OF CLINTON ELECTRICAL DEPARTMENT. CONTRACTOR SHALL STOCKPILE AS DIRECTED.
11. RECESSED HANDHOLE FOR FUTURE WORK WITHIN EXISTING ALLEYWAY. CONFIRM EXACT LOCATION WITH ENGINEER. HANDHOLE SHALL HAVE (1) DEDICATED 20A, 1P, 120V CIRCUIT TERMINAL IN WEATHERPROOF JUNCTION BOX, WITHIN HANDHOLE FOR FUTURE LIGHTING. CONTRACTOR SHALL ALSO INSTALL (1) 2" NM CONDUIT SWEEP FROM HANDHOLE TO 2 FEET BEYOND THE BACK OF THE CEMENT SIDEWALK WITHIN THE ALLEYWAY TO ALLOW FOR FUTURE CONNECTION.
12. ONE (1) 1" NM CONDUIT FOR IRRIGATION CONTROLLOER ETHERNET CABLE. CONDUIT SHALL BE RUN TO NEAREST TEL/DATA HANDHOLE. CONFIRM LOCATION OF TEL/DATA HANDHOLE WITH CLINTON DEPARTMENT OF PUBLIC WORKS.
13. ALL CONDUIT LOCATIONS ARE SHOWN TO ILLUSTRATE PROPOSED LAYOUTS AND CONNECTIONS. NO CONDUITS SHALL BE INSTALLED BENEATH PLANTING AREAS OR TREE PITS UNLESS APPROVED BY THE ENGINEER.
14. CONTRACTOR SHALL FURNISH AND INSTALL (1) NEW, 3", RACEWAY WITH PULLSTRING FROM NEW ENCLOSURE TO EXISTING UTILITY POLE. CONTRACTOR SHALL CONFIRM RISER HEIGHT, UP, EXISTING POLE AND RACEWAY MATERIAL WITH LOCAL UTILITY COMPANY.



NUMBER	DATE	MADE BY	CHECKED BY	DESCRIPTION
REVISIONS				

DRAWN BY:	PMG
DESIGNED BY:	PMG
CHECKED BY:	SA



HIGH STREET STREETSCAPE  
CLINTON, MA  
LIGHTING PLAN

BETA JOB NO.	6182
ISSUE DATE	JULY 2020
SHEET	1 of 6















NOTES:  
1. REFER TO LIGHTING PLAN SHEET 1 OF 6 FOR ADDITIONAL NOTES

NUMBER	DATE	MADE BY	CHECKED BY	DESCRIPTION	
REVISIONS					

DRAWN BY:	PMG
DESIGNED BY:	PMG
CHECKED BY:	SA



PREPARED BY:

**BETA**

www.BETA-Inc.com

**WB&A**

Wozny-Barbar & Associates, Inc.  
CONSULTING ENGINEERS

1078 Washington Street  
Hanover, MA 02339  
Tel: (781) 824-4144  
Fax: (781) 824-5792  
www.wbengineers.com

SCALE:

0 20 50 100

SCALE: 1" = 20'


UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

**HIGH STREET STREETSCAPE  
CLINTON, MA**

**LIGHTING PLAN**

BETA JOB NO.	6182
ISSUE DATE	JULY 2020
SHEET	4 of 6







NOTES:  
1. REFER TO LIGHTING PLAN SHEET 1 OF 6 FOR ADDITIONAL NOTES

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS	

DRAWN BY:	PMG
DESIGNED BY:	PMG
CHECKED BY:	SA




**HIGH STREET STREETSCAPE  
CLINTON, MA**

**LIGHTING PLAN**

BETA JOB NO.	6182
ISSUE DATE	JULY 2020
SHEET	5 of 6







NOTES:  
1. REFER TO LIGHTING PLAN SHEET 1 OF 6 FOR ADDITIONAL NOTES

NUMBER	DATE	MADE BY	CHECKED BY	DESCRIPTION
REVISIONS				

DRAWN BY: PMG  
DESIGNED BY: PMG  
CHECKED BY: SA




HIGH STREET STREETSCAPE  
CLINTON, MA  
LIGHTING PLAN








7/15/2020 9:38 AM C:\USER\STAMOR\DESKTOP\FINISHED PROJECT\IRRIGATION DESIGN\ALTERNATE 1 - STANDARD\IRRIGATION DESIGN\ALTERNATE 2.DWG (MONOCHROME.STB)



- IRRIGATION NOTES**
1. SEE IRRIGATION DETAILS AND SPECIFICATIONS FOR ADDITIONAL REQUIRED INFORMATION. SEE PLANS FOR ADDITIONAL INFORMATION.
  2. COORDINATE FINAL LOCATION OF IRRIGATION AND POLYMER CONCRETE VALVE BOXES WITH THE ENGINEER.
  3. ALL PIPE AND VALVE LOCATIONS ARE DIAGRAMMATIC FOR CLARITY; CONTRACTOR SHALL FIELD VERIFY.
  4. SPECIFIED VALVE BOX LOCATIONS AND COLORS SHALL BE APPROVED BY THE ENGINEER.
  5. IRRIGATION SYSTEM IS DESIGNED FOR DOMESTIC SUPPLY AT LESS THAN 1 GPM. SYSTEM TO PRODUCE 60-PSI DYNAMIC PRESSURE MINIMUM. CONTRACTOR SHALL TEST DYNAMIC PRESSURE BEFORE STARTING WORK AND REPORT ANY DEVIATION TO THE OWNER'S REPRESENTATIVE BEFORE CONTINUING.
  6. INSTALL NEW CONTROLLER IN ENCLOSURE AS LOCATED APPROXIMATELY ON PLANS, AS DIRECTED BY OWNER'S REPRESENTATIVE. HARD WIRE TO 120 VOLT, DEDICATED 20-AMP CIRCUIT, POWER SUPPLY USING LICENSED ELECTRICIAN.
  7. COORDINATE WITH ELECTRICAL CONTRACTOR TO PROVIDE MOCKUP OF PROPOSED LIGHT POLE IRRIGATION SYSTEM.
  8. GROUND IRRIGATION CONTROLLER TO EARTH. COORDINATE WITH SITE ELECTRICAL CONTRACTOR AND VERIFY UNDERGROUND UTILITIES.
  9. COORDINATE LOCATION OF ALL EXISTING AND FUTURE UTILITIES ON SITE. CONTACT PROPER AUTHORITIES AND UTILITY COMPANIES BEFORE THE START OF WORK.
  10. FLUSH ALL LATERAL LINES BEFORE INSTALLING DRIP IRRIGATION.
  11. CONTRACTOR MUST SUBMIT PRODUCT CUT SHEETS AS PER THE WRITTEN SPECIFICATIONS TO THE ENGINEER FOR APPROVAL PRIOR TO ORDERING MATERIAL AND BEGINNING WORK.
  12. MATERIAL SUBSTITUTIONS WHICH VARY FROM THE SPECIFIED PRODUCTS MUST BE SUBMITTED TO THE ENGINEER FOR APPROVAL AS PART OF THE SUBMITTAL PROCESS.
  13. ONCE APPROVED SUBMITTALS HAVE BEEN RETURNED TO THE CONTRACTOR, WORK MAY BEGIN. OWNER'S REPRESENTATIVE MUST BE NOTIFIED 7 DAYS IN ADVANCE OF THE START OF WORK TO COORDINATE ON-SITE SUPERVISION AND ADMINISTRATION.

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS	

DRAWN BY:  
TL  
DESIGNED BY:  
TL  
CHECKED BY:  
MI



TITLE

**HIGH STREET STREETSCAPE  
CLINTON, MA**

**OVERALL IRRIGATION  
LAYOUT PLAN**


BETA JOB NO. 6182

ISSUE DATE JULY 2020


SHEET NO. **IR-1.0**




7/15/2020 9:38 AM C:\USER\STAMORA\DESKTOP\PROJECTS\IRRIGATION DESIGN\ALTERNATE 1 - STANDARD\IRRIGATION DESIGN\ALTERNATE 2.DWG (MONOCHROME.STB)



1 HIGH STREET SOUTH WEST  
Scale 1" = 20'



2 HIGH STREET SOUTH EAST  
Scale 1" = 20'



3 UNION STREET  
Scale 1" = 20'

#### IRRIGATION NOTES


1. SEE IRRIGATION DETAILS AND SPECIFICATIONS FOR ADDITIONAL REQUIRED INFORMATION. SEE PLANS FOR ADDITIONAL INFORMATION.
2. COORDINATE FINAL LOCATION OF IRRIGATION AND POLYMER CONCRETE VALVE BOXES WITH THE ENGINEER.
3. ALL PIPE AND VALVE LOCATIONS ARE DIAGRAMMATIC FOR CLARITY; CONTRACTOR SHALL FIELD VERIFY.
4. SPECIFIED VALVE BOX LOCATIONS AND COLORS SHALL BE APPROVED BY THE ENGINEER.
5. IRRIGATION SYSTEM IS DESIGNED FOR DOMESTIC SUPPLY AT LESS THAN 1 GPM. SYSTEM TO PRODUCE 60-PSI DYNAMIC PRESSURE MINIMUM. CONTRACTOR SHALL TEST DYNAMIC PRESSURE BEFORE STARTING WORK AND REPORT ANY DEVIATION TO THE OWNER'S REPRESENTATIVE BEFORE CONTINUING.
6. INSTALL NEW CONTROLLER IN ENCLOSURE AS LOCATED APPROXIMATELY ON PLANS, AS DIRECTED BY OWNER'S REPRESENTATIVE. HARD WIRE TO 120 VOLT, DEDICATED 20-AMP CIRCUIT, POWER SUPPLY USING LICENSED ELECTRICIAN.
7. COORDINATE WITH ELECTRICAL CONTRACTOR TO PROVIDE MOCKUP OF PROPOSED LIGHT POLE IRRIGATION SYSTEM.
8. GROUND IRRIGATION CONTROLLER TO EARTH. COORDINATE WITH SITE ELECTRICAL CONTRACTOR AND VERIFY UNDERGROUND UTILITIES.
9. COORDINATE LOCATION OF ALL EXISTING AND FUTURE UTILITIES ON SITE, CONTACT PROPER AUTHORITIES AND UTILITY COMPANIES BEFORE THE START OF WORK.
10. FLUSH ALL LATERAL LINES BEFORE INSTALLING DRIP IRRIGATION.
11. CONTRACTOR MUST SUBMIT PRODUCT CUT SHEETS AS PER THE WRITTEN SPECIFICATIONS TO THE ENGINEER FOR APPROVAL PRIOR TO ORDERING MATERIAL AND BEGINNING WORK.
12. MATERIAL SUBSTITUTIONS WHICH VARY FROM THE SPECIFIED PRODUCTS MUST BE SUBMITTED TO THE ENGINEER FOR APPROVAL AS PART OF THE SUBMITTAL PROCESS.
13. ONCE APPROVED SUBMITTALS HAVE BEEN RETURNED TO THE CONTRACTOR, WORK MAY BEGIN. OWNER'S REPRESENTATIVE MUST BE NOTIFIED 7 DAYS IN ADVANCE OF THE START OF WORK TO COORDINATE ON-SITE SUPERVISION AND ADMINISTRATION.

#### IRRIGATION MATERIAL LIST

SYMBOL	MANUFACTURER/MODEL	DETAIL # (IR-2.0.2.1)
	1-inch Drip Control Zone Kit (Filter, PR)	<b>7,10</b>
	Multi-Outlet Emitter with 1/4-inch Drip Tubing	<b>12</b>
	Light Pole with Hanging Basket	<b>8</b>
	HDPE Ball Valve in Polymer Concrete Valve Box	<b>6</b>
	Quick Coupling Valve in Polymer Concrete Valve Box	<b>2,7</b>
	1-Station Decoder	<b>1,5</b>
	Baseline BaseStation 3200 with Cellular Modem	<b>1</b>
	Water Meter	<b>9</b>
	RPZ Backflow Preventer	
	1-inch Master Valves (N.O. & N.C.)	
	1-inch Flow Sensor and Pressure Sensor	
	Irrigation Lateral Line: 1-inch Fused HDPE	<b>9</b>
	Irrigation Mainline: 1-inch Fused HDPE and Valve Wire Conduit	
	Pipe Sleeve: PVC SCH 80 Solvent Weld Through Light Pole and Base	

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	TL
DESIGNED BY:	TL
CHECKED BY:	MI



TITLE	HIGH STREET STREETSCAPE CLINTON, MA  IRRIGATION LAYOUT PLAN
BETA JOB NO.	6182
ISSUE DATE	JULY 2020
SHEET NO.	IR-1.1







7/15/2020 9:38 AM C:\USER\STAMORA\DESKTOP\FINISHED PROJECTS\IRRIGATION DESIGN\ALTERNATE 1 - STANDARD\IRRIGATION DESIGN\ALTERNATE 2.DWG (MONOCHROME.STB)



IRRIGATION NOTES


1. SEE IRRIGATION DETAILS AND SPECIFICATIONS FOR ADDITIONAL REQUIRED INFORMATION. SEE PLANS FOR ADDITIONAL INFORMATION.
2. COORDINATE FINAL LOCATION OF IRRIGATION AND POLYMER CONCRETE VALVE BOXES WITH THE ENGINEER.
3. ALL PIPE AND VALVE LOCATIONS ARE DIAGRAMMATIC FOR CLARITY; CONTRACTOR SHALL FIELD VERIFY.
4. SPECIFIED VALVE BOX LOCATIONS AND COLORS SHALL BE APPROVED BY THE ENGINEER.
5. IRRIGATION SYSTEM IS DESIGNED FOR DOMESTIC SUPPLY AT LESS THAN 1 GPM. SYSTEM TO PRODUCE 60-PSI DYNAMIC PRESSURE MINIMUM. CONTRACTOR SHALL TEST DYNAMIC PRESSURE BEFORE STARTING WORK AND REPORT ANY DEVIATION TO THE OWNER'S REPRESENTATIVE BEFORE CONTINUING.
6. INSTALL NEW CONTROLLER IN ENCLOSURE AS LOCATED APPROXIMATELY ON PLANS, AS DIRECTED BY OWNER'S REPRESENTATIVE. HARD WIRE TO 120 VOLT, DEDICATED 20-AMP CIRCUIT, POWER SUPPLY USING LICENSED ELECTRICIAN.
7. COORDINATE WITH ELECTRICAL CONTRACTOR TO PROVIDE MOCKUP OF PROPOSED LIGHT POLE IRRIGATION SYSTEM.
8. GROUND IRRIGATION CONTROLLER TO EARTH. COORDINATE WITH SITE ELECTRICAL CONTRACTOR AND VERIFY UNDERGROUND UTILITIES.
9. COORDINATE LOCATION OF ALL EXISTING AND FUTURE UTILITIES ON SITE, CONTACT PROPER AUTHORITIES AND UTILITY COMPANIES BEFORE THE START OF WORK.
10. FLUSH ALL LATERAL LINES BEFORE INSTALLING DRIP IRRIGATION.
11. CONTRACTOR MUST SUBMIT PRODUCT CUT SHEETS AS PER THE WRITTEN SPECIFICATIONS TO THE ENGINEER FOR APPROVAL PRIOR TO ORDERING MATERIAL AND BEGINNING WORK.
12. MATERIAL SUBSTITUTIONS WHICH VARY FROM THE SPECIFIED PRODUCTS MUST BE SUBMITTED TO THE ENGINEER FOR APPROVAL AS PART OF THE SUBMITTAL PROCESS.
13. ONCE APPROVED SUBMITTALS HAVE BEEN RETURNED TO THE CONTRACTOR, WORK MAY BEGIN. OWNER'S REPRESENTATIVE MUST BE NOTIFIED 7 DAYS IN ADVANCE OF THE START OF WORK TO COORDINATE ON-SITE SUPERVISION AND ADMINISTRATION.

IRRIGATION MATERIAL LIST

SYMBOL	MANUFACTURER/MODEL	DETAIL # (IR-2.0.2.1)
	1-inch Drip Control Zone Kit (Filter, PR)	<b>7,10</b>
	Multi-Outlet Emitter with 1/4-inch Drip Tubing	
	Light Pole with Hanging Basket	<b>12</b>
	HDPE Ball Valve in Polymer Concrete Valve Box	<b>8</b>
	Quick Coupling Valve in Polymer Concrete Valve Box	<b>6</b>
	1-Station Decoder	<b>2,7</b>
	Baseline BaseStation 3200 with Cellular Modem	<b>1,5</b>
	Water Meter	<b>1</b>
	RPZ Backflow Preventer	
	1-inch Master Valves (N.O. & N.C.)	
	1-inch Flow Sensor and Pressure Sensor	
	Irrigation Lateral Line: 1-inch Fused HDPE	<b>9</b>
	Irrigation Mainline: 1-inch Fused HDPE and Valve Wire Conduit	
	Pipe Sleeve: PVC SCH 80 Solvent Weld Through Light Pole and Base	

NUMBER	DATE	MADE BY	CHECKED BY		REVISIONS

DRAWN BY:	TL
DESIGNED BY:	TL
CHECKED BY:	MI




TITLE	<b>HIGH STREET STREETSCAPE CLINTON, MA</b>
	<b>IRRIGATION LAYOUT PLAN</b>

BETA JOB NO.	6182
ISSUE DATE	JULY 2020
SHEET NO.	<b>IR-1.3</b>



7/15/2020 9:38 AM C:\USER\STAMORA\DESKTOP\PROJECTS\IRRIGATION DESIGN\ALTERNATE 1 - STANDARD\IRRIGATION DESIGN\ALTERNATE 2.DWG (MONOCHROME.STB)



## IRRIGATION NOTES


1. SEE IRRIGATION DETAILS AND SPECIFICATIONS FOR ADDITIONAL REQUIRED INFORMATION. SEE PLANS FOR ADDITIONAL INFORMATION.
2. COORDINATE FINAL LOCATION OF IRRIGATION AND POLYMER CONCRETE VALVE BOXES WITH THE ENGINEER.
3. ALL PIPE AND VALVE LOCATIONS ARE DIAGRAMMATIC FOR CLARITY; CONTRACTOR SHALL FIELD VERIFY.
4. SPECIFIED VALVE BOX LOCATIONS AND COLORS SHALL BE APPROVED BY THE ENGINEER.
5. IRRIGATION SYSTEM IS DESIGNED FOR DOMESTIC SUPPLY AT LESS THAN 1 GPM. SYSTEM TO PRODUCE 60-PSI DYNAMIC PRESSURE MINIMUM. CONTRACTOR SHALL TEST DYNAMIC PRESSURE BEFORE STARTING WORK AND REPORT ANY DEVIATION TO THE OWNER'S REPRESENTATIVE BEFORE CONTINUING.
6. INSTALL NEW CONTROLLER IN ENCLOSURE AS LOCATED APPROXIMATELY ON PLANS, AS DIRECTED BY OWNER'S REPRESENTATIVE. HARD WIRE TO 120 VOLT, DEDICATED 20-AMP CIRCUIT, POWER SUPPLY USING LICENSED ELECTRICIAN.
7. COORDINATE WITH ELECTRICAL CONTRACTOR TO PROVIDE MOCKUP OF PROPOSED LIGHT POLE IRRIGATION SYSTEM.
8. GROUND IRRIGATION CONTROLLER TO EARTH. COORDINATE WITH SITE ELECTRICAL CONTRACTOR AND VERIFY UNDERGROUND UTILITIES.
9. COORDINATE LOCATION OF ALL EXISTING AND FUTURE UTILITIES ON SITE, CONTACT PROPER AUTHORITIES AND UTILITY COMPANIES BEFORE THE START OF WORK.
10. FLUSH ALL LATERAL LINES BEFORE INSTALLING DRIP IRRIGATION.
11. CONTRACTOR MUST SUBMIT PRODUCT CUT SHEETS AS PER THE WRITTEN SPECIFICATIONS TO THE ENGINEER FOR APPROVAL PRIOR TO ORDERING MATERIAL AND BEGINNING WORK.
12. MATERIAL SUBSTITUTIONS WHICH VARY FROM THE SPECIFIED PRODUCTS MUST BE SUBMITTED TO THE ENGINEER FOR APPROVAL AS PART OF THE SUBMITTAL PROCESS.
13. ONCE APPROVED SUBMITTALS HAVE BEEN RETURNED TO THE CONTRACTOR, WORK MAY BEGIN. OWNER'S REPRESENTATIVE MUST BE NOTIFIED 7 DAYS IN ADVANCE OF THE START OF WORK TO COORDINATE ON-SITE SUPERVISION AND ADMINISTRATION.

## IRRIGATION MATERIAL LIST

SYMBOL	MANUFACTURER/MODEL	DETAIL # (IR-2.0.2.1)
	1-inch Drip Control Zone Kit (Filter, PR)	<b>7,10</b>
	Multi-Outlet Emitter with 1/4-inch Drip Tubing	<b>12</b>
	Light Pole with Hanging Basket	<b>8</b>
	HDPE Ball Valve in Polymer Concrete Valve Box	<b>6</b>
	Quick Coupling Valve in Polymer Concrete Valve Box	<b>2,7</b>
	1-Station Decoder	<b>1,5</b>
	Baseline BaseStation 3200 with Cellular Modem	<b>1</b>
	Water Meter	<b>9</b>
	RPZ Backflow Preventer	
	1-inch Master Valves (N.O. & N.C.)	
	1-inch Flow Sensor and Pressure Sensor	
	Irrigation Lateral Line: 1-inch Fused HDPE	
	Irrigation Mainline: 1-inch Fused HDPE and Valve Wire Conduit	
	Pipe Sleeve: PVC SCH 80 Solvent Weld Through Light Pole and Base	

NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:	TL
DESIGNED BY:	TL
CHECKED BY:	MI




TITLE	<b>HIGH STREET STREETSCAPE CLINTON, MA</b>
<b>IRRIGATION LAYOUT PLAN</b>	

BETA JOB NO.	6182
ISSUE DATE	JULY 2020
SHEET NO.	<b>IR-1.4</b>



7/15/2020 9:38 AM C:\USER\STAMOR\DESKTOP\FINISHED PROJECTS\IRRIGATION DESIGN\ALTERNATE 1 - STANDARD\IRRIGATION DESIGN\ALTERNATE 2.DWG (MONOCHROME.STB)




#### IRRIGATION NOTES

- SEE IRRIGATION DETAILS AND SPECIFICATIONS FOR ADDITIONAL REQUIRED INFORMATION. SEE PLANS FOR ADDITIONAL INFORMATION.
- COORDINATE FINAL LOCATION OF IRRIGATION AND POLYMER CONCRETE VALVE BOXES WITH THE ENGINEER.
- ALL PIPE AND VALVE LOCATIONS ARE DIAGRAMMATIC FOR CLARITY; CONTRACTOR SHALL FIELD VERIFY.
- SPECIFIED VALVE BOX LOCATIONS AND COLORS SHALL BE APPROVED BY THE ENGINEER.
- IRRIGATION SYSTEM IS DESIGNED FOR DOMESTIC SUPPLY AT LESS THAN 1 GPM. SYSTEM TO PRODUCE 60-PSI DYNAMIC PRESSURE MINIMUM. CONTRACTOR SHALL TEST DYNAMIC PRESSURE BEFORE STARTING WORK AND REPORT ANY DEVIATION TO THE OWNER'S REPRESENTATIVE BEFORE CONTINUING.
- INSTALL NEW CONTROLLER IN ENCLOSURE AS LOCATED APPROXIMATELY ON PLANS, AS DIRECTED BY OWNER'S REPRESENTATIVE. HARD WIRE TO 120 VOLT, DEDICATED 20-AMP CIRCUIT, POWER SUPPLY USING LICENSED ELECTRICIAN.
- COORDINATE WITH ELECTRICAL CONTRACTOR TO PROVIDE MOCKUP OF PROPOSED LIGHT POLE IRRIGATION SYSTEM.
- GROUND IRRIGATION CONTROLLER TO EARTH. COORDINATE WITH SITE ELECTRICAL CONTRACTOR AND VERIFY UNDERGROUND UTILITIES.
- COORDINATE LOCATION OF ALL EXISTING AND FUTURE UTILITIES ON SITE, CONTACT PROPER AUTHORITIES AND UTILITY COMPANIES BEFORE THE START OF WORK.
- FLUSH ALL LATERAL LINES BEFORE INSTALLING DRIP IRRIGATION.
- CONTRACTOR MUST SUBMIT PRODUCT CUT SHEETS AS PER THE WRITTEN SPECIFICATIONS TO THE ENGINEER FOR APPROVAL PRIOR TO ORDERING MATERIAL AND BEGINNING WORK.
- MATERIAL SUBSTITUTIONS WHICH VARY FROM THE SPECIFIED PRODUCTS MUST BE SUBMITTED TO THE ENGINEER FOR APPROVAL AS PART OF THE SUBMITTAL PROCESS.
- ONCE APPROVED SUBMITTALS HAVE BEEN RETURNED TO THE CONTRACTOR, WORK MAY BEGIN. OWNER'S REPRESENTATIVE MUST BE NOTIFIED 7 DAYS IN ADVANCE OF THE START OF WORK TO COORDINATE ON-SITE SUPERVISION AND ADMINISTRATION.

#### IRRIGATION MATERIAL LIST

SYMBOL	MANUFACTURER/MODEL	DETAIL # (IR-2.0.2.1)
	1-inch Drip Control Zone Kit (Filter, PR)	<b>7,10</b>
	Multi-Outlet Emitter with 1/4-inch Drip Tubing	<b>12</b>
	Light Pole with Hanging Basket	<b>8</b>
	HDPE Ball Valve in Polymer Concrete Valve Box	<b>6</b>
	Quick Coupling Valve in Polymer Concrete Valve Box	<b>2,7</b>
	1-Station Decoder	<b>1,5</b>
	Water Meter	<b>1</b>
	RPZ Backflow Preventer	
	1-inch Master Valves (N.O. & N.C.)	
	1-inch Flow Sensor and Pressure Sensor	
	Irrigation Lateral Line: 1-inch Fused HDPE	<b>9</b>
	Irrigation Mainline: 1-inch Fused HDPE and Valve Wire Conduit	
	Pipe Sleeve: PVC SCH 80 Solvent Weld Through Light Pole and Base	



NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:  
TL  
DESIGNED BY:  
TL  
CHECKED BY:  
MI

REGISTERED PROFESSIONAL  
MICHAEL IGO  
CIVIL  
No. 46486  
REGISTERED PROFESSIONAL ENGINEER

PREPARED BY  
**BETA**  
www.BETA-Inc.com

SUBCONSULTANT  
**Aqueous**  
AQUEOUS CONSULTANTS, LLC  
2 Dundee Park Drive, Suite 301B  
Andover, MA 01810  
(978) 470-1695

SCALE  
SCALE IN FEET: 1"=20'  
20 0 20 40  
UNLESS OTHERWISE NOTED OR CHANGED BY REPRODUCTION

TITLE  
**HIGH STREET STREETSCAPE  
CLINTON, MA**  
**IRRIGATION LAYOUT PLAN**



BETA JOB NO. 6182  
ISSUE DATE JULY 2020  
SHEET NO. **IR-1.5**







7/15/2020 9:38 AM C:\USER\TAMORA\DESKTOP\FINISHED PROJECTS\IRRIGATION DESIGN\ALTERNATE 1 - STANDARD\IRRIGATION DESIGN\ALTERNATE 2.DWG (MONOCHROME.STB)



12 LAMP POST IRRIGATION DETAIL  
NOT TO SCALE




NUMBER	DATE	MADE BY	CHECKED BY	REVISIONS

DRAWN BY:  
TL

DESIGNED BY:  
TL

CHECKED BY:  
MI



TITLE

**HIGH STREET STREETSCAPE  
CLINTON, MA**

**IRRIGATION DETAILS**

BETA JOB NO. 6182

ISSUE DATE JULY 2020

SHEET NO. **IR-2.1**